

US EPA RECORDS CENTER REGION 5



436539

**SOIL BORING AND
MONITORING WELL INSTALLATION**

**DAYTON ELECTROPLATE, INC.
1030 VALLEY STREET
DAYTON, OHIO**

December 16, 1999



Mr. Randy Watterworth
Ohio Environmental Protection Agency
Division of Emergency and Remedial Response
Southwest District Office
401 East Fifth Street
Dayton, Ohio 45402-2911

**Regarding: Soil Boring and Monitoring Well Installation
Dayton Electroplate, Inc.
1030 Valley Street, Dayton, Ohio
Ohio EPA Mobilization Order No. 557-09
PN 60008.11**

Dear Mr. Watterworth:

PSARA Technologies, Inc. (PSARA) is pleased to submit this letter report describing the installation of six soil borings and monitoring wells at the subject site (Figure 1). Midwest Environmental Drilling, under the direction of PSARA geologist, Mr. Tim O'Dowd, installed the borings/monitoring wells in the area around two former underground storage tank (UST) pits and other areas of interest (Figure 2). The following describes the field activities. All work was performed in accordance with PSARA's Work Plan dated August 16, 1999, and Ohio Environmental Protection Agency (EPA) Mobilization Order No. 557-09.

SUMMARY OF FIELD ACTIVITIES

Soil Boring and Soil Sampling

From August 23 through August 26, 1999, PSARA installed six soil borings/monitoring wells (MW-1 through MW-6) at the site. The soil boring locations are shown on the map in Figure 2.

Prior to the start of drilling, PSARA notified the Ohio Utilities Protection Service (OUPS), which instructed its members to mark the locations of underground utilities at the site. To further guard against drilling through mismarked or unknown underground utilities, the first 3 ft of each boring were advanced at a slow rate.

Borings were advanced using 4.25-in.-ID hollow-stem augers to an average depth of 42 ft. Soil samples were collected continuously from each boring using a 2-in.-diameter split-spoon sampler.

**E N V I R O N M E N T A L
C O N S U L T A N T S**

10925 REED HARTMAN HIGHWAY
SUITE 220
CINCINNATI, OH 45242
TEL: 513.791.4418
FAX: 513.791.5797
E-MAIL: mailbox@psara.com

PSARA's onsite geologist described the samples in the field as the borings were advanced. In general, the soils encountered beneath the site consisted of undifferentiated fill material overlying poorly sorted sand and gravel. The fill appeared to be largely construction debris with visible brick, glass, and slag present. Fine-grained, well-sorted, multi-colored sand discovered between 2 and 3 ft below grade at boring SB-3 is believed to be foundry sand. The native soil comprises poorly sorted sand with gravel and silt. Numerous clayey layers and lenses and a few cobble layers were observed at various depths in each boring. Detailed descriptions of the subsurface material from each boring are presented in the Soil Boring Logs in Attachment A.

In general, groundwater was encountered within the sands at a depth of approximately 32 ft. Upon drilling into saturated conditions, "heaving" sands were observed to be flowing into the annulus of the hollow-stem augers. Where heaving was observed, split-spoon sampling was suspended so that the tools would not be lost.

The split-spoon sampler was decontaminated between each sample with a nonphosphate detergent wash and tap water rinse to prevent cross-contamination of samples. The augers, drill rods, and split-spoons were cleaned prior to and following drilling activities using a steam/pressure washer.

Soil vapor screening was conducted in the field using a photoionization detector (PID). The PID is factory calibrated annually. Also, before each use, a PSARA technician calibrates the PID according to the following procedure: fill then purge a plastic Tedlar bag with zero air; fill the Tedlar bag with a standard consisting of 100 ppm isobutylene balanced with zero air; insert the probe of the PID into the Tedlar bag and close it with an airtight seal; and adjust the instrument's span (calibration device) to read 56 ppm. During sample screening, the split-spoon sampler was opened to reveal the sample core, and the probe of the PID was held within 1 in. of the soil surface. The soil vapor analysis results are included on the Soil Boring Logs in Attachment A.

Monitoring Well Installation and Development

PSARA installed groundwater monitoring wells MW-1 through MW-6 to intercept first groundwater in the corresponding soil borings. Well construction consisted of 2-in.-diameter, flush-threaded polyvinylchloride (PVC) riser pipe coupled to a 10-ft section of 0.010-in. machine-slotted PVC well screen. The well screen was surrounded by a filter pack of coarse, washed quartz sand and sealed with a 2-ft layer of bentonite. Because the wells were installed into an aquifer with heaving sands, an unknown amount of each screen section is assumed to be surrounded by natural sand.

Following placement of the filter pack and bentonite seal, the remaining augers were removed from the boring, and the annulus was allowed to cave naturally. The remaining annulus was then filled with bentonite chips and topped with Portland cement. A locking well seal was placed on each well to prevent tampering. Further well protection was provided by a 5.5-in. bolt-down, flush-mounted protective cover installed in a 2-ft by 2-ft concrete pad. Two wells, MW-3 and MW-6, were given further protection using standpipes and steel posts instead of the flush-mounted covers. Well construction details are presented on the Well Construction Diagrams in Attachment A.

On August 26 and 27, 1999, a PSARA geologist developed the newly installed wells to remove excess fine particulates. Prior to well development, PSARA measured the depth

to groundwater and checked each well for the presence of light nonaqueous-phase liquid (LNAPL) with an oil/water interface probe. No LNAPL was encountered on this date. Depth-to-groundwater measurements are reported on the Well Development Logs in Attachment B. Ground surface elevations, top-of-casing elevations, and depth-to-groundwater measurements obtained on September 29, 1999, are summarized in Table 1.

Monitoring well development consisted of surging each well with a Teflon surge block, then purging water from the well with a decontaminated submersible pump and dedicated tygon tubing. The pump was decontaminated between wells to prevent cross-contamination using a nonphosphate detergent wash, tap water rinse, and deionized water rinse. The well was determined to be properly developed when one of the following criteria had been met: 1) at least five well volumes of water had been removed, 2) the pH readings were within 0.2 S.U. of the corresponding measurement for the previous well volume and the specific conductance and temperature readings were within 10 percent of the corresponding measurements for the previous well volume, or 3) the well was purged dry. The surge block could not be used in MW-1 because of a slight bend in the PVC casing. The Well Development Logs are included in Attachment B.

Monitoring Well Surveying

PSARA contracted a registered surveyor to survey the locations and elevations of the newly installed wells. Wells were surveyed relative to mean sea level and Ohio State Plane coordinates. As a convention, a point on the north side of the PVC casing was used as a standard survey point. PSARA returned to the site on December 2, 1999, to survey the ground surface elevation at each well location. The results of this survey are included in Attachment C and listed in Table 1.

Management of Investigation-Derived Waste (IDW)

All auger cuttings from the installation of the six monitoring wells at the site were placed in 55-gal drums for future disposal by the Ohio EPA. Four composite samples were collected from these drums and analyzed for the toxicity characteristic by Quanterra Incorporated in North Canton, Ohio, in accordance with the U.S. EPA's Toxicity Characteristic Leaching Procedure (TCLP), Method 1311 (55FR 26986). All samples were non-detect for TCLP parameters. The laboratory analytical report is included in Attachment D.

Purge water from well development activities was collected in 5-gal buckets and transferred to an onsite sanitary sewer. This water was discharged to the sewer with the approval of the City of Dayton.

Variances

Due to difficulties associated with the heaving sands encountered in each boring, several modifications to the Approved Work Plan were required to complete the scope of work. Each variance to the Work Plan, along with the corrective action is listed below:

- Due to sand heave, complete filter packs were not installed. The natural sand that entered the auger annulus during well construction was allowed to remain.


Mr. Randy Watterworth
December 16, 1999
Page 4

- During drilling, it was noted that nearly the entire soil column consisted of sand and gravel. Upon determining that the drillers were unable to install a Portland Cement grout over the well seal, the decision was made in the field to allow the annulus to cave naturally.
- Difficulties were encountered during the installation of MW-1 and MW-6. Specifically, the bentonite seal became bridged during installation and jammed the well in the augers. These wells were consequently removed, redrilled, and reinstalled.

We appreciate the opportunity to assist the Ohio EPA with this project. If we can be of further assistance, please do not hesitate to call me.

Sincerely,

PSARA TECHNOLOGIES, INC.



Timothy P. O'Dowd
Project Geologist

Attachments

TABLES


Table 1. Groundwater Elevations
August 27, 1999
Dayton Electroplate, Inc.
1030 Valley Street, Dayton, Ohio

| Well No. | Top of Casing Elevation, ft ^a | Ground surface Elevation, ft ^a | Depth to Groundwater, ft | Groundwater Elevation, ft ^a | LNAPL ^b Thickness, ft |
|----------|---|--|-----------------------------|---|-------------------------------------|
| MW-1 | 656.46 | 656.73 | 30.12 | 626.34 | 0 |
| MW-2 | 657.38 | 657.62 | 33.69 | 623.69 | 0 |
| MW-3 | 658.48 | 655.21 | 35.19 | 617.98 | 0 |
| MW-4 | 654.44 | 654.25 | 27.77 | 626.67 | 0 |
| MW-5 | 657.50 | 657.74 | 30.84 | 626.66 | 0 |
| MW-6 | 660.21 | 657.53 | 33.31 | 626.90 | 0 |


^a Elevation measured relative to mean sea level.

^b LNAPL = light nonaqueous-phase liquid.

FIGURES



SCALE 1:24000



QUADRANGLE LOCATION



Legend

USGS 7.5 Minute Quadrangle

Dayton North, Ohio

39084-G2-TF-024

revised 1992


OHIO EPA

Figure 1. Site Location Map
Dayton Electroplate, Inc.
1030 Valley Street
Dayton, Ohio

Drawn by:
AKA

Date:
October 26, 1999

Scale:
NTS



LEGEND



Monitoring Well Location

OHIO EPA

Figure 2.
Site Layout Map
Dayton Electroplate Site
Dayton, Montgomery County, Ohio

| | | | | |
|-----------------|---------|-------------|-----------|--------|
| Project Number: | Scale: | Checked By: | Drawn By: | Date: |
| 60008.11 | 1"=100' | SAS | RJS | 8/4/99 |

ATTACHMENT A

Soil Boring Logs, Well Construction Diagrams, and ODNR Well Logs

Soil Boring Log

Project No. 60008.11
Boring No. MW-1
Page 1 of 3

General Information

| | |
|--|--|
| Client: Ohio Environmental Protection Agency | Boring No.: MW-1 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date(s) Drilled: August 23, 1999 |
| PSARA Geologist: Tim O'Dowd | Drilling Method / Borehole Size: 4.25" I.D. HSA |
| Drilling Contractor: Midwest Environmental Drilling | Total Depth of Borehole (ft): 42 |
| Sampling Device: 2" X 24" Split Spoon | Depth to Water (ft): 31 ft |
| Headspace Screening Instrument: <input checked="" type="checkbox"/> PID <input type="checkbox"/> FID | Well Installed: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Well No.: MW-1 |

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| | 0 | 2 | | | Concrete, no sample taken. | | |
| MW-1-0204 | 2 | 4 | 17 | 7-12-16-18 | Fill material, 1/4" - 1" gravel, with some brown silty clay loam and gray sand, very unconsolidated, poorly sorted. | 0 | |
| MW-1-0406 | 4 | 6 | 20 | 10-10-12-12 | Fill (4'-5.5'), same as above, w/ some red brick fragments. Sand w/ gravel (5.5'-6'), light brown, loose, poorly sorted sand, with approx. 50% 1/4"-1/2" gravel, probably still fill material. | 0 | |
| MW-1-0608 | 6 | 8 | 15 | 12-12-13-14 | Sand w/ gravel (6'-8'), same as above. | 0 | |
| MW-1-0810 | 8 | 10 | 14 | 10-12-18-18 | Sand & gravel (8'-9.25'), poorly sorted, grayish sand w/ 1/16" - 1" cobbles, some limestone cobbles about 1" in dia., some smaller sandstone cobbles fragments at 8.5', slight natural gas odor. | 0 | |
| MW-1-1012 | 10 | 12 | 18 | 25-16-16-16 | Sand & gravel, same as above, upper 4" darker brown then gray sand, w/ 50% gravel, some large limestone cobbles about 1.5" dia. | 0 | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
 Boring No. MW-1
 Page 2 of 3

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| MW-1-1214 | 12 | 14 | 18 | 25-16-16-16 | Sand w/ gravel (12'-12.5'), same as above. Sand (12.5'-13') fairly abrupt contact w/ a multi-colored, medium-grained, sand, wet, w/ approx. 30% gravel (1/16"-1/2" dia.), damp, slight natural gas odor. | 0 | |
| MW-1-1416 | 14 | 16 | 16 | 20-20-20-20 | Sand & gravel (14'-15.25'), very poorly sorted sand w/ limestone, chert and sandstone cobbles, 1/16"-1/8" in dia. | 0 | |
| MW-1-1618 | 16 | 18 | 12 | 10-10-11-12 | Sand & gravel (16'-16.5'), same as above. Sand (16.5'-17'), fine-grained, well sorted, light brown sand, loose, damp, w/ some quartz grains. | 0 | |
| MW-1-1820 | 18 | 20 | 12 | 12-12-12-14 | Sand & gravel (18'-19'), poorly sorted, grayish sand, w/ 1/16"-1" dia. cobbles, limestone & chert, small 1" layer of fine-grained sand from above in upper part of spoon. | 0 | |
| MW-1-2022 | 20 | 22 | 18 | 20-17-12-12 | Sand & gravel (20'-21.5'), same as above, small fine-grain sand stringer @ 20.75', very poorly sorted throughout, same natural gas odor. | 0 | |
| MW-1-2224 | 22 | 24 | 24 | 25-19-20-26 | Sand & gravel (22'-23'), same as above. Sand & gravel (23'-24'), abrupt contact w/ a slightly better-sorted sand & gravel, iron staining, smaller cobbles w/ a multi-colored sand. | 0 | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
 Boring No. MW-2
 Page 1 of 3

General Information

| | |
|--|--|
| Client: Ohio Environmental Protection Agency | Boring No.: MW-2 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date(s) Drilled: August 23, 1999 |
| PSARA Geologist: Tim O'Dowd | Drilling Method / Borehole Size: 4.25" I.D. HSA |
| Drilling Contractor: Midwest Environmental Drilling | Total Depth of Borehole (ft): 42 |
| Sampling Device: 2" X 24" Split Spoon | Depth to Water (ft): 30 ft |
| Headspace Screening Instrument: <input checked="" type="checkbox"/> PID <input type="checkbox"/> FID | Well Installed: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Well No.: MW-2 |

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|--|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| | 0 | 2 | | | Concrete & fill, no sample taken. | | |
| MW-2-0204 | 2 | 4 | 20 | 2-2-3-3 | Clay, light brown silty clay, plastic, w/ some large 1" cobbles, upper 3" of sample darker brown. | 0 | |
| MW-2-0406 | 4 | 6 | 6 | 2-2-3-4 | Poor recovery, 3" of clay similar to above, sand & gravel last 3", poorly sorted light brown sand w/ large 1" dia. limestone cobbles. | 0 | |
| MW-2-0608 | 6 | 8 | 6 | 4-6-7-7 | Clay, dark brown silty clay, very soft & plastic, w/ approx. 5% 1/8" dia. gravel. | 0 | |
| MW-2-0810 | 8 | 10 | 12 | 5-6-6-7 | Clay (8'-8.25'), same as above. Sand & gravel (8.25'-9'), light brown, poorly sorted sand & gravel w/ 1/8" - 1" limestone & chert cobbles, slight "natural gas" odor. | 0 | |
| MW-2-1012 | 10 | 12 | 15 | 10-10-12-12 | Sand & gravel, poorly sorted, multi-colored sand, w/ 50% 1/16" - 1" dia. gravel & cobbles. | 0 | |
| MW-2-1214 | 12 | 14 | 12 | 6-11-12-12 | Sand & gravel, same as above. | 0 | |
| MW-2-1416 | 14 | 16 | 10 | 15-13-10-10 | Sand & gravel, same as above. | 0 | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
 Boring No. MW-2
 Page 2 of 3

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|--|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| MW-2-1618 | 16 | 18 | 17 | 7-9-9-10 | Sand & gravel, slightly better sorting, some moisture, some iron staining, same "natural gas" odor. -end of day- | 0 | |
| MW-2-1820 | 18 | 20 | 15 | 5-5-5-7 | Sand & gravel, same as above. | 0 | |
| MW-2-2022 | 20 | 22 | 15 | 8-11-15-15 | Sand & gravel, same as above, large 1" limestone cobbles throughout. | 0 | |
| MW-2-2224 | 22 | 24 | 17 | 6-25-30-30 | Sand & gravel, same as above, with a small, light brown silty clay lense @ 22.25'. | 0 | |
| MW-2-2426 | 24 | 26 | 15 | 12-18-15-15 | Sand & gravel, same as above, w/o the lense. | 0 | |
| MW-2-2628 | 26 | 28 | 18 | 15-20-25-27 | Sand & gravel, same as above, consistently unsorted in entire boring so far. | 0 | |
| MW-2-2830 | 28 | 30 | 18 | 12-20-15-15 | Sand & gravel, same as above, not as many large cobbles as above. | 0 | |
| MW-2-3032 | 30 | 32 | 12 | 12-9-7-7 | Sand & gravel, multi-colored sand, w/ 1/8"-1/2" mixed cobbles, entire sample wet, water @ 30'. | 0 | |
| MW-2-3234 | 32 | 34 | 15 | 10-13-9-7 | Sand & gravel, same as above, very wet. | 0 | |
| MW-2-3436 | 34 | 36 | 15 | 6-7-10-6 | Sand & gravel, saturated, more gravel than above, approx. 50% 1/4"-1/2" dia. | 0 | |
| MW-2-3638 | 36 | 38 | 12 | 6-8-6-9 | Sand & gravel, same as above, saturated. | 0 | |
| MW-2-3840 | 38 | 40 | 15 | 8-8-8-8 | Sand & gravel, same as above, w/ 1" sand stringers @ 38.25' & 39', saturtated. | 0 | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11

Boring No. MW-3

Page 1 of 3

General Information

| | |
|--|--|
| Client: Ohio Environmental Protection Agency | Boring No.: MW-3 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date(s) Drilled: August 24, 1999 |
| PSARA Geologist: Tim O'Dowd | Drilling Method / Borehole Size: 4.25" I.D. HSA |
| Drilling Contractor: Midwest Environmental Drilling | Total Depth of Borehole (ft): 40 |
| Sampling Device: 2" X 24" Split Spoon | Depth to Water (ft): 32.5 ft |
| Headspace Screening Instrument: <input checked="" type="checkbox"/> PID <input type="checkbox"/> FID | Well Installed: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Well No.: MW-3 |

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| | 0 | 2 | | | Fill, no sample taken. | | |
| MW-3-0204 | 2 | 4 | 12 | 6-3-3-3 | Gravel & fill material (2'-2.25'), dark brown fill & gravel. Sand (2.25'-3') banded purple, gray, & brown, fine-grained sand, probably founders sand. Sand & gravel (3'-3.25'), black, stained, fine-grained sand, w/ a 1" limestone cobble, slight unknown odor. | 0 0.7 | |
| MW-3-0406 | 4 | 6 | 10 | 2-2-2-2 | Sand, same as above, yellow, gray, black, no odor. | 0 | |
| MW-3-0608 | 6 | 8 | 20 | 3-3-3-3 | Sand, same as above, no odor. | 0 | |
| MW-3-0810 | 8 | 10 | 22 | 4-2-2-2 | Sand, same as above, no odor. | 0 | |
| MW-3-1012 | 10 | 12 | 20 | 5-3-2-2 | Sand, same as above, no odor. | 0 | |
| MW-3-1214 | 12 | 14 | 12 | 5-1-1-1 | Sand, same as above, 2" of "slag" at bottom of sample, porous pumice -like material, resultant of extreme heat, wet. | 0 | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
 Boring No. MW-3
 Page 2 of 3

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|--|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| MW-3-1416 | 14 | 16 | 16 | 25-16-16-16 | Sand (14'-14.25'), same as above, dry. | 0 | |
| | | | | | Clay (14.25'-15'), light reddish brown, silty clay w/ approx. 20% 1/16"-1/4" gravel, plastic, weathered. | | |
| | | | | | Gravel (15'-15.25'), light brown yellowish clay matrix w/ approx. 70% gravel, 3 inches. | | |
| MW-3-1618 | 16 | 18 | 20 | 8-6-5-5 | Clay (16'-16.5'), dark brown silty clay w/ gravel. | 0 | |
| | | | | | Sand & gravel (16.5'-17.75'), yellowish brown med. -grained sand w/ approx. 50% 1/16"-1/4" dia. cobbles, very dry. | | |
| MW-3-1820 | 18 | 20 | 12 | 8-7-5-6 | Sand & gravel, same as above. | 0 | |
| MW-3-2022 | 20 | 22 | 12 | 5-9-10-10 | Sand & gravel, same as above. | 0 | |
| MW-3-2224 | 22 | 24 | 24 | 18-14-16-16 | Sand & gravel, same as above, w/ somewhat larger (1/2" dia.) gravel throughout. | 0 | |
| MW-3-2426 | 24 | 26 | 15 | 18-17-17-17 | Sand & gravel, same as above, sand is coarser, more gravel, approx. 60% 1/4"-1" dia. | 0 | |
| MW-3-2628 | 26 | 28 | 18 | 16-19-25-27 | Sand & gravel, same as above, w/ slightly smaller gravel. | 0 | |
| MW-3-2830 | 28 | 30 | 20 | 17-17-18-19 | Sand & gravel, same as above. | n/a | |
| | | | | | PID temporarily out of order, moisture in display, removed from rainy site conditions. | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
Boring No. MW-4
Page 1 of 3

General Information

| | |
|--|--|
| Client: Ohio Environmental Protection Agency | Boring No.: MW-4 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date(s) Drilled: August 25, 1999 |
| PSARA Geologist: Tim O'Dowd | Drilling Method / Borehole Size: 4.25" I.D. HSA |
| Drilling Contractor: Midwest Environmental Drilling | Total Depth of Borehole (ft): 38 |
| Sampling Device: 2" X 24" Split Spoon | Depth to Water (ft): 26 ft |
| Headspace Screening Instrument: <input checked="" type="checkbox"/> PID <input type="checkbox"/> FID | Well Installed: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Well No.: MW-4 |

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| | 0 | 2 | | | Gravel, no sample taken | | |
| MW-4-0204 | 2 | 4 | | 3-2-2-2 | No recovery. | | |
| MW-4-0406 | 4 | 6 | 8 | 2-1-1-1 | Fill, dark brown, rusty, silty clay loam, w/ gravel, slag material, and glass. | 0.3 | |
| MW-4-0608 | 6 | 8 | 12 | 1-1-1-1 | Fill, same as above. | 0 | |
| MW-4-0810 | 8 | 10 | 10 | 1-1-1-1 | Fill, same as above, wet in lower 2 inches of sample, black pumice -like material throughout. | 0 | |
| MW-4-1012 | 10 | 12 | 8 | 1-1-1-1 | Fill, same as above, brick fragments, black pumice-like material. Some silty wet clay in last inch of sample. | 0 | |
| MW-4-1214 | 12 | 14 | 17 | 1-1-1-3 | Clay, light brownish gray silty clay, w/ approx. 10% 1/4" - 1/2" dia. gravel, some black coal-like fragments and iron-stained fragments, probably not native material. | 0 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
 Boring No. MW-4
 Page 2 of 3

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| MW-4-1416 | 14 | 16 | 12 | 1-2-3-5 | Clay (14'-14.25'), light brown silty clay, weathered, plastic. | 0 | |
| | | | | | Clay (14.25'-15'), light yellowish brown sandy clay, w/ approx. 50% gravel (1/16"-1/4" dia.), more sand w/ depth. | | |
| MW-4-1618 | 16 | 18 | 2 | 3-13-20-23 | Very little recovery, lots of cave-in from above, w/ one large 2" dia. limestone cobble protruding from the shoe of the spoon. | 0 | |
| MW-4-1820 | 18 | 20 | 12 | 13-15-19-20 | Sand & gravel, light yellowish brown coarse sand w/ approx. 40% 1/16"-1" cobbles, "natural gas" type odor, very poorly sorted. | 0 | |
| MW-4-2022 | 20 | 22 | 10 | 15-15-18-20 | Sand & gravel, same as above, large 1 1/2" dia. limestone cobbles in last 2", 1" band of yellow sand in upper part of spoon. | 0 | |
| MW-4-2224 | 22 | 24 | 20 | 8-10-10-10 | Clay (22'-22.5'), dark brown sandy clay w/ gravel wet, approx. 20% 1/2" dia. gravel. Sand & gravel (22.5'-23.75'), multi-colored, coarse sand w/ 1/8"-1" gravel & cobbles, wet. | 0 | |
| MW-4-2426 | 24 | 26 | 6 | 15-16-18-18 | Sand & gravel. limited recovery, same as above. | 0 | |
| MW-4-2628 | 26 | 28 | 17 | 8-9-10-10 | Sand & gravel, coarse-grained, multi-colored sand w/ 50% 1/4"-3/4" gravel, better sorted than above, saturated. | 0 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11

Boring No. MW-5

Page 1 of 3

General Information

| | |
|--|--|
| Client: Ohio Environmental Protection Agency | Boring No.: MW-5 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date(s) Drilled: August 25, 1999 |
| PSARA Geologist: Tim O'Dowd | Drilling Method / Borehole Size: 4.25" I.D. HSA |
| Drilling Contractor: Midwest Environmental Drilling | Total Depth of Borehole (ft): 42 |
| Sampling Device: 2" X 24" Split Spoon | Depth to Water (ft): 32 ft |
| Headspace Screening Instrument: <input checked="" type="checkbox"/> PID <input type="checkbox"/> FID | Well Installed: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Well No.: MW-5 |

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|------------|--|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| | 0 | 2 | | | No sample, gravel parking lot. | | |
| MW-5-0204 | 2 | 4 | 16 | 4-3-3-3 | Fill (2'-2.25'), light brown / gray sand, fill & gravel. Brick (2.25'-2.5'), red brick fragments. Fill (2.5'-3.25'), black sandy fill & gravel, looks stained but no odor. | 0 | |
| MW-5-0406 | 4 | 6 | 16 | 4-1-1-1 | Fill, black material like above, brick fragments, sand, & gravel, very mixed. | 0 | |
| MW-5-0608 | 6 | 8 | 18 | 6-12-18-20 | Fill (6'-6.5'), same as above. Sand & gravel (6.5'-7.5'), light brown, dry, med. grained sand, w/ approx. 30% 1/4"-1" dia. cobbles, mostly limestone, native material. | 0 | |
| MW-5-0810 | 8 | 10 | 12 | 6-12-18-14 | Sand & gravel, same as above. | 0 | |
| MW-5-1012 | 10 | 12 | 15 | 8-12-16-18 | Sand & gravel, same as above. | 0 | |
| MW-5-1214 | 12 | 14 | 12 | 8-12-14-7 | Sand & gravel, same w/ one 2" limestone cobble @ 12'. | 0 | |
| | | | | | | | |
| | | | | | | | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11
 Boring No. MW-5
 Page 2 of 3

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| MW-5-1416 | 14 | 16 | 16 | 10-12-16-23 | Sand & gravel, same as above, fairly strong natural gas odor. | 0 | |
| MW-5-1618 | 16 | 18 | 18 | 15-15-15-18 | Sand & gravel, changing over to a multicolored sand w/ approx. 50% assorted cobbles, some iron staining in lower 3" of sample, same odor. | 0 | |
| MW-5-1820 | 18 | 20 | 10 | 10-12-14-14 | Sand & gravel, same as above. | 0 | |
| MW-5-2022 | 20 | 22 | 15 | 9-9-10-12 | Sand & gravel, same as above. | 0 | |
| MW-5-2224 | 22 | 24 | 16 | 10-18-20-22 | Sand & gravel, same as above. | 0 | |
| MW-5-2426 | 24 | 26 | 18 | 17-19-50/5 | Sand & gravel, same as above, w/ larger cobbles, 1"-1 1/2", throughout. | 0 | |
| MW-5-2628 | 26 | 28 | 18 | 19-19-20-23 | Sand & gravel, same as above, smaller cobbles in last foot of sample, 1/4"-1/2" dia. | 0 | |
| MW-5-2830 | 28 | 30 | 15 | 16-20-22-23 | Sand & gravel, same as above. | 0 | |
| MW-5-3032 | 30 | 32 | 10 | 20-20-50/5 | Sand & gravel, same as above. | 0 | |
| MW-5-3234 | 32 | 34 | 18 | 9-16-18-20 | Sand & gravel, abrupt contact with a coarse-grained, saturated, multi-colored sand, w/ approx. 50% 1/16"-1" gravel and cobbles, very poorly sorted. | 0 | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |
| | | | | | | | |

Notes

| |
|--|
| |
| |
| |

Soil Boring Log

Project No. 60008.11

Boring No. MW-6

Page 1 of 3

General Information

| | |
|--|--|
| Client: Ohio Environmental Protection Agency | Boring No.: MW-6 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date(s) Drilled: August 26, 1999 |
| PSARA Geologist: Tim O'Dowd | Drilling Method / Borehole Size: 4.25" I.D. HSA |
| Drilling Contractor: Midwest Environmental Drilling | Total Depth of Borehole (ft): 42 |
| Sampling Device: 2" X 24" Split Spoon | Depth to Water (ft): 32 ft |
| Headspace Screening Instrument: <input checked="" type="checkbox"/> PID <input type="checkbox"/> FID | Well Installed: <input checked="" type="checkbox"/> Yes <input type="checkbox"/> No Well No.: MW-6 |

Summary of Boring

| Sample No. | Sample Depth (ft) | | Recovery (in) | Blow Count | Sample/Core Description | Headspace Reading (ppm) | |
|------------|-------------------|----|---------------|-------------|---|-------------------------|---------------|
| | From | To | | | | Total Organic | Total Methane |
| | 0 | 2 | | | No sample, grass and top soil. | | |
| MW-6-0204 | 2 | 4 | 18 | 15-17-19-20 | Topsoil (2'-2.25'), dark brown silty clay loam. | 0 | |
| | | | | | Sand & gravel (2.25'-3.5'), light brown, med.-grained sand w/ approx. 30% gravel, large limestone gravel @ 2.25'-2.5', strong "natural gas" odor. | | |
| MW-6-0406 | 4 | 6 | 18 | 18-17-20-23 | Sand & gravel, same as above, w/ more gravel approx. 50% 1/8"-1" dia. gravel, slight odor. | 0 | |
| MW-6-0608 | 6 | 8 | 15 | 17-19-23-24 | Sand & gravel, same as above, stronger odor. | 0 | |
| MW-6-0810 | 8 | 10 | 6 | 13-19-16-20 | Sand & gravel, same as above, same odor as above. | 0 | |
| MW-6-1012 | 10 | 12 | 6 | 13-16-17-17 | Sand & gravel, same as above. | 0 | |
| MW-6-1214 | 12 | 14 | 16 | 15-16-17-30 | Sand & gravel, same as above. | 0 | |
| MW-6-1416 | 14 | 16 | 14 | 30-17-19-20 | Sand & gravel, same as above. | 0 | |
| MW-6-1618 | 16 | 18 | 16 | 17-14-10-10 | Sand & gravel, same as above, strong "natural gas" odor. | 0 | |

Notes

| |
|--|
| |
| |
| |


Well Construction Diagram

Project No. **60008.11**
Well No. **MW-1**

General Information

| | |
|---|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-1 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date Completed: 8/23/99 |
| PSARA Geologist: Tim O'Dowd | Drilling Method: Hollow Stem Auger |
| Drilling Contractor: Midwest Environmental | Depth to Static Water (ft): 30.12 ft |

Construction Details



NOT TO SCALE

^a elevation above mean sea level


Well Construction Diagram

Project No. 60008.11
Well No. MW-2

General Information

| | |
|---|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-2 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date Completed: 8/24/99 |
| PSARA Geologist: Tim O'Dowd | Drilling Method: Hollow Stem Auger |
| Drilling Contractor: Midwest Environmental | Depth to Static Water (ft): 31.63 ft |

Construction Details



NOT TO SCALE

^a elevation above mean sea level


Well Construction Diagram

Project No. **60008.11**
Well No. **MW-3**

General Information

| | |
|---|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-3 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date Completed: 8/24/99 |
| PSARA Geologist: Tim O'Dowd | Drilling Method: Hollow Stem Auger |
| Drilling Contractor: Midwest Environmental | Depth to Static Water (ft): 35.19 ft |

Construction Details



NOT TO SCALE

^a elevation above mean sea level


Well Construction Diagram

Project No. 60008.11
Well No. MW-4

General Information

| | |
|---|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-4 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date Completed: 8/25/99 |
| PSARA Geologist: Tim O'Dowd | Drilling Method: Hollow Stem Auger |
| Drilling Contractor: Midwest Environmental | Depth to Static Water (ft): 30.23 ft |

Construction Details



NOT TO SCALE

^a elevation above mean sea level


Well Construction Diagram

Project No. 60008.11
Well No. MW-5

General Information

| | |
|---|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-5 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date Completed: 8/25/99 |
| PSARA Geologist: Tim O'Dowd | Drilling Method: Hollow Stem Auger |
| Drilling Contractor: Midwest Environmental | Depth to Static Water (ft): 33.48 ft |

Construction Details



NOT TO SCALE

^a elevation above mean sea level


Well Construction Diagram

Project No. 60008.11
Well No. MW-6

General Information

| | |
|---|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-6 |
| Site Location: Dayton Electroplate, 1030 Valley Street | Date Completed: 8/26/99 |
| PSARA Geologist: Tim O'Dowd | Drilling Method: Hollow Stem Auger |
| Drilling Contractor: Midwest Environmental | Depth to Static Water (ft): 33.31 ft |

Construction Details



NOT TO SCALE

^a elevation above mean sea level

COUNTY Montgomery

TOWNSHIP 2

SECTION/Lot No. 35
(CIRCLE ONE)

OWNER/BUILDER Dorton Electroplate
(CIRCLE ONE OR BOTH)

PROPERTY ADDRESS 1030 Valley ST Dorton OH
(ADDRESS OF WELL LOCATION A)

LOCATION OF PROPERTY Same

CONSTRUCTION DETAILS MW-1

CASING Borehole Diameter 8 in.
1 Diameter 2 in. Length 26.64 ft. Wall Thickness sch 40 in. Material Bentonite Volume used 8 50lb bag
2 Diameter _____ in. Length _____ ft. Wall Thickness _____ in. Method of installation HSM
Type: 1 Steel 2 Galv. 3 PVC 4 _____
Depth: placed from 2 ft. to 24
GRAVEL PACK (Filter Pack)
Material #5 sand Volume used 12 50lb bag
Method of installation HSM
Depth: placed from 36 ft. to 24
Joints: 1 Threaded 2 Welded 3 Solvent 4 Other _____
Liner: Length _____ Type _____ Wall Thickness _____ in.
SCREEN
Type (wire wrapped, louvered, etc.) slotted Material PVC
Length 10 ft. Diameter 2 in.
Set between 26 ft. and 36 ft. Slot 0.010
Pitless Device ☐ Adapter ☐ Preassembled unit
Use of Well mw market cover
☐ Rotary ☐ Cable ☒ Augered ☐ Driven ☐ Dug ☐ Other _____
Date of Completion 8-23-99

WELL LOG

INDICATE DEPTH(S) AT WHICH WATER IS ENCOUNTERED.

Show color, texture, hardness, and formation:
sandstone, shale, limestone, gravel, clay, sand, etc.

From To

Sand & Gravel, Brown 0 36.97

MW-1

WELL TEST

☐ Bailing ☐ Pumping ☐ Other _____
Test rate N/A gpm Duration of test _____ hr
Drawdown _____
Measured from: ☐ top of casing ☒ ground level ☐ Other _____
Static Level (depth to water) _____ ft. Date: _____
Quality (clear, cloudy, taste, odor) _____

*(Attach a copy of the pumping test record, per section 1521.05, ORC)

PUMP

Type of pump N/A Capacity _____ gpm
Pump set at _____ ft.
Pump installed by _____

SKETCH SHOWING WELL LOCATION

Show distances well lies from numbered state highways,
street intersections, county roads, etc.

N

W

E

S

If additional space is needed to complete well log, use next consecutively numbered form

I hereby certify the information given is accurate and correct to the best of my knowledge.

Drilling Firm MED

Signed Jim Ruckel

Address 11405 Scatter Creek

Date 8-23-99

City, State, Zip Cincinnati OH 45246

ODH Registration Number N/A

TYPE OR USE PEN
SELF TRANSCRIBING
PRESS HARD

Ohio Department of Natural Resources, Division of Water
1939 Fountain Square Drive, Columbus, Ohio 43224 Phone (614) 265-6739

Permit Number N/ACOUNTY MontgomeryTOWNSHIP 2SECTION/LOT No. 35
(CIRCLE ONE)OWNER/BUILDER Dorton Electroplate
(CIRCLE ONE OR BOTH)PROPERTY ADDRESS 1030 Valley St Dorton Ave
(ADDRESS OF WELL LOCATION A)LOCATION OF PROPERTY Same

CONSTRUCTION DETAILS

CASING Borehole Diameter 8 in.
☒ Diameter 2 in. Length 29 ft. Wall Thickness Sch 40 in. Material Bentonite Volume used 9.5066 bag
☐ Diameter _____ in. Length _____ ft. Wall Thickness _____ in. Method of installation HSA
 Type: ☐ Steel ☐ Galv. ☒ PVC ☐ Other _____
☐ Depth: placed from 26 ft. to 2
GRAVEL PACK (Filter Pack)
 Material #5 Sand Volume used 10.50 lb bag
 Method of installation HSA
☐ Depth: placed from 36.06 ft. to 26
 Joints: ☐ Threaded ☐ Welded ☐ Solvent ☐ Other _____
 Liner: Length _____ Type _____ Wall Thickness Sch 40 in.
SCREEN
 Type (wire wrapped, louvered, etc.) Slotted Material PVC
 Length 10 ft. Diameter 2 in.
 Set between 29 ft. and 39 ft. Slot 0.010
 Pitless Device ☐ Adapter ☐ Preassembled unit
 Use of Well MW manhole cave.
☐ Rotary ☐ Cable ☒ Augered ☐ Driven ☐ Dug ☐ Other _____
 Date of Completion 8-24-99

WELL LOG*

INDICATE DEPTH(S) AT WHICH WATER IS ENCOUNTERED.

Show color, texture, hardness, and formation:

sandstone, shale, limestone, gravel, clay, sand, etc.

From To

Sand & Gravel, Brown 0 39.64
MW-2

WELL TEST

☐ Bailing ☐ Pumping* ☐ Other _____
 Test rate N/A gpm Duration of test _____ hr
 Drawdown _____
 Measured from: ☐ top of casing ☐ ground level ☐ Other _____
 Static Level (depth to water) _____ ft. Date: _____
 Quality (clear, cloudy, taste, odor) _____

*(Attach a copy of the pumping test record, per section 1521.05, ORC)

PUMP

Type of pump _____ Capacity _____ gpm
 Pump set at _____ ft.
 Pump installed by N/A

SKETCH SHOWING WELL LOCATION

Show distances well lies from numbered state highways,
street intersections, county roads, etc.

N

See Attachment

W

E

S

*If additional space is needed to complete well log, use next consecutively numbered form

I hereby certify the information given is accurate and correct to the best of my knowledge.

Drilling Firm MEDSigned James R. SmithAddress 11405 Century CircleDate 8-24-99City, State, Zip Cincinnati OH 45246ODH Registration Number N/A

Completion of this form is required by section 1521.05, Ohio Revised Code - file within 30 days after completion of drilling.

ORIGINAL COPY TO - ODNR, DIVISION OF WATER, 1939 FOUNTAIN SQ. DRIVE, COLS., OHIO 43224

Blue - Customers only. Pink - Drillers only. Green - Local Health Dept. only.

COUNTY Montgomery TOWNSHIP 2

SECTION/LOT No. 35
(CIRCLE ONE)

OWNER/BUILDER Dartan Electroplate
(CIRCLE ONE OR BOTH)

PROPERTY ADDRESS 1030 Valley St. Dayton OH
(ADDRESS OF WELL LOCATION A)

LOCATION OF PROPERTY Same

CONSTRUCTION DETAILS

CASING Borehole Diameter 8 in.
☒ Diameter 2" in. Length 31 ft. Wall Thickness sch 40 in. Material Bentinite Volume used 11.50 lb bag
☐ Diameter _____ in. Length _____ ft. Wall Thickness _____ in. Method of Installation HSA
Type: ☐ Steel ☐ Galv. ☒ PVC ☐ _____
Joints: ☐ _____ ☒ Threaded ☐ Welded ☐ Solvent ☐ Other _____
Liner: Length _____ Type _____ Wall Thickness _____ in. Depth: placed from 31 ft. to 2
SCREEN **GRAVEL PACK (Filter Pack)**
Type (wire wrapped, louvered, etc.) Slotted Material PVC Material #5 Sand Volume used 8.50 lb bag
Length 10 ft. Diameter 2" in. Method of Installation HSA
Set between 31 ft. and 41 ft. Slot 0.010 Depth: placed from 41 ft. to 31
Well Log* **Pitless Device** ☐ Adapter ☐ Preassembled unit
Type (wire wrapped, louvered, etc.) Slotted Material PVC Use of Well MW Manhole cover
Length 10 ft. Diameter 2" in. ☐ Rotary ☐ Cable ☐ Augered ☐ Driven ☐ Dug ☐ Other _____
Set between 31 ft. and 41 ft. Slot 0.010 Date of Completion 8-24-99

WELL LOG*

INDICATE DEPTH(S) AT WHICH WATER IS ENCOUNTERED.

Show color, texture, hardness, and formation:
sandstone, shale, limestone, gravel, clay, sand, etc.

From To

Sand & Gravel, Brown
mw-3

0 41

WELL TEST

☐ Bailing ☐ Pumping* ☐ Other _____
Test rate NA gpm Duration of test _____ h
Drawdown _____
Measured from: ☐ top of casing ☐ ground level ☐ Other _____
Static Level (depth to water) _____ ft. Date: _____
Quality (clear, cloudy, taste, odor) _____

*(Attach a copy of the pumping test record, per section 1521.05, ORC)

PUMP

Type of pump NA Capacity _____ gp
Pump set at _____
Pump installed by _____

SKETCH SHOWING WELL LOCATION

Show distances well lies from numbered state highways,
street intersections, county roads, etc.

N

See Attachment

W

E

S

*If additional space is needed to complete well log, use next consecutively numbered form.

I hereby certify the information given is accurate and correct to the best of my knowledge.

Drilling Firm MEID

Signed John Ruck

Address 11405 Century Circle

Date 8-24-99

City, State, Zip Cincinnati OH 45246

ODH Registration Number NA

SECTION/LOT No. 35
(CIRCLE ONE)

PROPERTY ADDRESS 1030 Valley St Dayton
(ADDRESS OF WELL LOCATION ▲)

CONSTRUCTION DETAILS

WELL LOG*

Show color, texture, hardness, and formation:
sandstone, shale, limestone, gravel, clay, sand, etc.

| From | To |
|------|----|
|------|----|

Sand & Gravel
mw - 4

037

WELL TEST

☐ Bailing ☐ Pumping ☐ Other _____
 Test rate N/A gpm Duration of test _____ hr
 Drawdown _____
 Measured from: ☐ top of casing ☐ ground level ☐ Other _____
 Static Level (depth to water) _____ ft. Date: _____
 Quality (clear, cloudy, taste, odor) _____

*(Attach a copy of the pumping test record, per section 1521.05, ORC)

PUMP

Type of pump DLH Capacity _____ gpm
Pump set at _____ ft
Pump installed by _____

SKETCH SHOWING WELL LOCATION

Show distances well lies from numbered state highways, street intersections, county roads, etc.

N

See Attachment

W

E

5

*If additional space is needed to complete well log, use next consecutively numbered form

I hereby certify the information given is accurate and correct to the best of my knowledge.

Signed Jason Kuehls

Date 8-25-99

ODH Registration Number *WA*

Completion of this form is required by section 1521.05, Ohio Revised Code - file within 30 days after completion of drilling.

ORIGINAL COPY TO - ODNR, DIVISION OF WATER, 1939 FOUNTAIN SQ. DRIVE, COLS., OHIO 43224

TYPE OR USE PEN
SELF TRANSCRIBING
PRESS HARD

Ohio Department of Natural Resources, Division of Water
1939 Fountain Square Drive, Columbus, Ohio 43224 Phone (614) 265-6739

Permit Number N/A

COUNTY Montgomery TOWNSHIP 2 SECTION/LOT No. 35
(CIRCLE ONE)

OWNER/BUILDER Dorton Electroplating PROPERTY ADDRESS 1030 valley ST Dorton P.I.
(CIRCLE ONE OR BOTH) (ADDRESS OF WELL LOCATION A)

LOCATION OF PROPERTY Same

CONSTRUCTION DETAILS

CASING Borehole Diameter 8" in. **GROUT**
1 Diameter 2' in. Length 26 ft. Wall Thickness sch 40 in. Material Bentonite Volume used 10-50 lb bag
2 Diameter _____ in. Length _____ ft. Wall Thickness _____ in. Method of installation HSA
Type: ☐ Steel ☐ Galv. ☒ PVC ☐ Other _____
Joints: ☒ Threaded ☐ Welded ☐ Solvent ☐ Other _____
Liner: Length _____ Type _____ Wall Thickness _____ in. Depth: placed from 2 ft. to 30 ft.
SCREEN **GRAVEL PACK (Filter Pack)**
Type (wire wrapped, louvered, etc.) Slotted Material PVC Material #5 sand Volume used 6-50 lb bag
Length 10 ft. Diameter 2" in. Method of installation HSA
Set between 31 ft. and 41 ft. Slot 0.010 Depth: placed from 41 ft. to 30 ft.
Pitless Device ☐ Adapter ☐ Preassembled unit
Use of Well MW Max hole cover
☐ Rotary ☒ Cable ☒ Augered ☐ Driven ☐ Dug ☐ Other _____
Date of Completion 8-25-99

WELL LOG*

INDICATE DEPTH(S) AT WHICH WATER IS ENCOUNTERED.

Show color, texture, hardness, and formation:
sandstone, shale, limestone, gravel, clay, sand, etc.

From To

Sand & Gravel, Brown
MW-5

0 41

WELL TEST

☐ Bailing ☒ Pumping* ☐ Other _____
Test rate N/A gpm Duration of test _____ hrs
Drawdown _____
Measured from: ☐ top of casing ☐ ground level ☐ Other _____
Static Level (depth to water) _____ ft. Date: _____
Quality (clear, cloudy, taste, odor) _____

*(Attach a copy of the pumping test record, per section 1521.05, ORC)

PUMP

Type of pump N/A Capacity _____ gpm
Pump set at _____ ft.
Pump installed by _____

SKETCH SHOWING WELL LOCATION

Show distances well lies from numbered state highways,
street intersections, county roads, etc.

N

See Attachment

W

S

*If additional space is needed to complete well log, use next consecutively numbered form.

I hereby certify the information given is accurate and correct to the best of my knowledge.

Drilling Firm MEP

Signed John R. Smith

Address 11405 CENTURY CIRCLE

Date 8-25-99

City, State, Zip Cincinnati OH 45246

ODH Registration Number N/A

Completion of this form is required by section 1521.05, Ohio Revised Code - file within 30 days after completion of drilling.
ORIGINAL COPY TO - ODNR, DIVISION OF WATER, 1939 FOUNTAIN SQ. DRIVE, COLS., OHIO 43224
Blue - Customer's copy Pink - Driller's copy Green - Local Health Dept. copy

TYPE OR USE PEN
SELF TRANSCRIBING
PRESS HARD

Ohio Department of Natural Resources, Division of Water
1939 Fountain Square Drive, Columbus, Ohio 43224 Phone (614) 265-6739

Permit Number

N/A

COUNTY MontgomeryTOWNSHIP 2SECTION/LOT No. 35
(OR ACE ONE)OWNER/BUILDER Dorton ElectrolatePROPERTY ADDRESS 1030 Valley St Dayton OH
(ADDRESS OF WELL LOCATION A)LOCATION OF PROPERTY Same

CONSTRUCTION DETAILS

CASING Borehole Diameter 8 in. **GROUT**
☐ Diameter 2 in. Length 32 ft. Wall Thickness Sch 40 in. Material Bedrock Volume used 9-50 lb bags
☐ Diameter _____ in. Length _____ ft. Wall Thickness _____ in. Method of installation HSM
 Type: ☐ Steel ☐ Galv. ☒ **PVC** ☐ Other _____ Depth: placed from 30 ft. to 2 ft.
 Joints: ☐ Threaded ☐ Welded ☐ Solvent ☐ Other _____ **GRAVEL PACK (Filter Pack)**
 Liner: Length _____ Type _____ Wall Thickness Sch 40 in. Material #5 sand Volume used 7 50 lb bags
SCREEN Method of installation HSM
 Type (wire wrapped, louvered, etc.) slotted Material PVC Depth: placed from 30 ft. to 42 ft.
 Length 10 ft. Diameter 2 in. **Pitless Device** ☐ Adapter ☐ Preassembled unit
 Set between 32 ft. and 42 ft. Slot 0.010 **Use of Well** MW manhole covers
☐ Rotary ☐ Cable ☒ Augered ☐ Driven ☐ Dug ☐ Other _____
 Date of Completion 8-26-99

WELL LOG*

INDICATE DEPTH(S) AT WHICH WATER IS ENCOUNTERED.

Show color, texture, hardness, and formation:
sandstone, shale, limestone, gravel, clay, sand, etc.

From To

Sand & Gravel, Brown 0 42
MW #6

WELL TEST

☐ Bailing ☐ Pumping* ☐ Other _____
 Test rate N/A gpm Duration of test _____ hrs
 Drawdown _____ ft.
 Measured from: ☐ top of casing ☐ ground level ☐ Other _____
 Static Level (depth to water) _____ ft. Date: _____
 Quality (clear, cloudy, taste, odor) _____

*(Attach a copy of the pumping test record, per section 1521.05, ORC)

PUMP

Type of pump N/A Capacity _____ gpm
 Pump set at _____ ft.
 Pump installed by _____

SKETCH SHOWING WELL LOCATION

Show distances well lies from numbered state highways,
street intersections, county roads, etc.

N

See Attachment

W

S

If additional space is needed to complete well log, use next consecutively numbered form.

I hereby certify the information given is accurate and correct to the best of my knowledge.

Drilling Firm MEDSigned Jim RuskAddress 11405 Century CircleDate 8-26-99City, State, Zip Cincinnati OH 45246ODH Registration Number N/A

Completion of this form is required by section 1521.05, Ohio Revised Code - file within 30 days after completion of drilling.

TOTAL P.07

ATTACHMENT B
Well Development Logs

Project No. 60008.11
Well No. MW-1

| | |
|--|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-1 |
| Site Location: Dayton Electroplate, 1030 Valley St. | Date Developed: 8/27/99 Time: 1037 to 1047 |
| PSARA Technician(s): Tim O'Dowd | Weather: 70's Overcast |


| | |
|--|---|
| Measuring Point: <input checked="" type="checkbox"/> Top of Casing <input type="checkbox"/> Other: | Measurement Instr.: <input type="checkbox"/> Tape <input type="checkbox"/> Electronic <input checked="" type="checkbox"/> O/W Probe |
| Depth to Water (ft): D1 = 29.66 | Height of Water Column (ft): H = (D2 - D1) = 7.43 |
| Depth to Well Bottom (ft): D2 = 37.09 | Volume of Water in Well (gal): V = (H x F) = 1.21 |
| Product Present: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Depth to Product (ft): NA Product Thickness (in): NA |

4" well: $F = 0.651$

| Well Volume | pH | Conductivity (µmho) | Temperature (°C) | Appearance / Odor |
|--|------|---------------------|------------------|--------------------------------------|
| First Bailer | 6.87 | 1,130 | 20.5 | Very turbid light brown, no odor |
| Volume No. 1 | 6.79 | 877 | 18.3 | Very turbid light brown, no odor |
| Volume No. 2 | 6.74 | 1,090 | 16.8 | Turbid light brown, no odor |
| Volume No. 3 | 6.71 | 1,090 | 16.7 | Turbid light brown, no odor |
| Volume No. 4 | 6.67 | 990 | 17.1 | Slightly turbid light brown, no odor |
| Volume No. 5 | 6.69 | 996 | 17.0 | Slightly turbid light brown, no odor |
| Total Volume Purged (gal): 8.0 | | | | |
| Well Purged Dry: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | |

well could not be surged, slightly bent, drill rods would not fit.

Ent'd by: TPO
Ck'd by:
Date: 4-23-99



| | |
|--|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-2 |
| Site Location: Dayton Electroplate, 1030 Valley St. | Date Developed: 8/27/99 Time: 1000 to 1017 |
| PSARA Technician(s): Tim O'Dowd | Weather: 70's Sunny |

| | |
|--|---|
| Measuring Point: <input checked="" type="checkbox"/> Top of Casing <input type="checkbox"/> Other: | Measurement Instr.: <input type="checkbox"/> Tape <input type="checkbox"/> Electronic <input checked="" type="checkbox"/> O/W Probe |
| Depth to Water (ft): D1 = 30.69 | Height of Water Column (ft): H = (D2 - D1) = 8.44 |
| Depth to Well Bottom (ft): D2 = 39.13 | Volume of Water in Well (gal): V = (H x F) = 1.38 |
| Product Present: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Depth to Product (ft): NA Product Thickness (in): NA |

2" well: $F = 0.163$

4" well: $F = 0.651$

| Well Volume | pH | Conductivity (µmho) | Temperature (°C) | Appearance / Odor |
|--|------|---------------------|------------------|--------------------------------------|
| First Bailer | 6.88 | 1,040 | 20.1 | Turbid light brown, no odor |
| Volume No. 1 | 6.95 | 968 | 17.2 | Turbid light brown, no odor |
| Volume No. 2 | 6.94 | 936 | 17.3 | Turbid light brown, no odor |
| Volume No. 3 | 6.91 | 1,050 | 16.7 | Slightly turbid light brown, no odor |
| Volume No. 4 | 6.93 | 1,050 | 16.5 | Slightly turbid light brown, no odor |
| Volume No. 5 | 6.94 | 1,060 | 16.5 | Mostly clear, no odor |
| Total Volume Purged (gal): 8.0 | | | | |
| Well Purged Dry: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | |

Notes

[illegible]

Project No. 60008.11
Well No. MW-3

| | |
|--|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-3 |
| Site Location: Dayton Electroplate, 1030 Valley St. | Date Developed: 8/27/99 Time: 0755 to 0822 |
| PSARA Technician(s): Tim O'Dowd | Weather: 70's Overcast |

| | |
|--|---|
| Measuring Point: <input checked="" type="checkbox"/> Top of Casing <input type="checkbox"/> Other: | Measurement Instr.: <input type="checkbox"/> Tape <input type="checkbox"/> Electronic <input checked="" type="checkbox"/> O/W Probe |
| Depth to Water (ft): D1 = 35.19 | Height of Water Column (ft): H = (D2 - D1) = 9.88 |
| Depth to Well Bottom (ft): D2 = 45.07 | Volume of Water in Well (gal): V = (H x F) = 1.61 |
| Product Present: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Depth to Product (ft): NA Product Thickness (in): NA |

4" well: $F = 0.651$

| Well Volume | pH | Conductivity (µmho) | Temperature (°C) | Appearance / Odor |
|--|------|---------------------|------------------|----------------------------------|
| First Bailer | 6.71 | 1,280 | 17.4 | Very Turbid light brown, no odor |
| Volume No. 1 | 6.67 | 1,060 | 16.7 | Very Turbid light brown, no odor |
| Volume No. 2 | 6.59 | 1,250 | 16.5 | Very Turbid light brown, no odor |
| Volume No. 3 | 6.52 | 1,120 | 16.1 | Very Turbid light brown, no odor |
| Volume No. 4 | 6.50 | 1,230 | 15.8 | Very Turbid light brown, no odor |
| Volume No. 5 | 6.49 | 1,210 | 15.9 | Very Turbid light brown, no odor |
| Total Volume Purged (gal): 9.0 | | | | |
| Well Purged Dry: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | |

[illegible]

Project No. 60008.11
Well No. MW-4

| | |
|--|---|
| Client: Ohio Environmental Protection Agency | Well No.: MW-4 |
| Site Location: Dayton Electroplate, 1030 Valley St. | Date Developed: 8/27/99 Time: 0835 to 0906 |
| PSARA Technician(s): Tim O'Dowd | Weather: 70's Overcast |

| | |
|--|---|
| Measuring Point: <input checked="" type="checkbox"/> Top of Casing <input type="checkbox"/> Other: | Measurement Instr.: <input type="checkbox"/> Tape <input type="checkbox"/> Electronic <input checked="" type="checkbox"/> O/W Probe |
| Depth to Water (ft): D1 = 27.77 | Height of Water Column (ft): H = (D2 - D1) = 9.86 |
| Depth to Well Bottom (ft): D2 = 37.63 | Volume of Water in Well (gal): V = (H x F) = 1.61 |
| Product Present: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Depth to Product (ft): NA Product Thickness (in): NA |

4" well: $F = 0.651$

| Well Volume | pH | Conductivity (µmho) | Temperature (°C) | Appearance / Odor |
|--|------|---------------------|------------------|--------------------------------------|
| First Bailer | 6.79 | 1,030 | 17.4 | Turbid light brown, no odor |
| Volume No. 1 | 6.94 | 826 | 16.7 | Slightly Turbid light brown, no odor |
| Volume No. 2 | 6.85 | 865 | 16.5 | Slightly Turbid light brown, no odor |
| Volume No. 3 | 6.80 | 871 | 16.1 | Clear, no odor |
| Volume No. 4 | 6.84 | 884 | 15.8 | Clear, no odor |
| Volume No. 5 | 6.84 | 894 | 15.9 | Clear, no odor |
| Total Volume Purged (gal): 9.0 | | | | |
| Well Purged Dry: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | |

| | |
|--|---------------|
| | Ent'd by: TPO |
| | Ck'd by: |
| | Date: 4-23-99 |

Project No. 60008.11
Well No. MW-6

| | | |
|--|--------------------------------|----------------------------------|
| Client: Ohio Environmental Protection Agency | Well No.: MW-6 | |
| Site Location: Dayton Electroplate, 1030 Valley St. | Date Developed: 8/26/99 | Time: 1700 to 1720 |
| PSARA Technician(s): Tim O'Dowd | Weather: 80's Sunny | |

| | |
|--|---|
| Measuring Point: <input checked="" type="checkbox"/> Top of Casing <input type="checkbox"/> Other: | Measurement Instr.: <input type="checkbox"/> Tape <input type="checkbox"/> Electronic <input checked="" type="checkbox"/> O/W Probe |
| Depth to Water (ft): D1 = 33.31 | Height of Water Column (ft): H = (D2 - D1) = 11.77 |
| Depth to Well Bottom (ft): D2 = 45.08 | Volume of Water in Well (gal): V = (H x F) = 1.92 |
| Product Present: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | Depth to Product (ft): NA Product Thickness (in): NA |

4" well: $F = 0.651$

| Well Volume | pH | Conductivity (µmho) | Temperature (°C) | Appearance / Odor |
|--|------|---------------------|------------------|----------------------------------|
| First Bailer | 6.94 | 1,610 | 21.3 | Very turbid light brown, no odor |
| Volume No. 1 | 6.88 | 1,670 | 17.3 | Very turbid light brown, no odor |
| Volume No. 2 | 6.83 | 1,670 | 17.7 | Very turbid light brown, no odor |
| Volume No. 3 | 6.81 | 1,730 | 16.7 | Very turbid light brown, no odor |
| Volume No. 4 | 6.76 | 1,600 | 16.8 | Very turbid light brown, no odor |
| Volume No. 5 | 6.72 | 1,740 | 16.8 | Very turbid light brown, no odor |
| Total Volume Purged (gal): 10.0 | | | | |
| Well Purged Dry: <input type="checkbox"/> Yes <input checked="" type="checkbox"/> No | | | | |

[illegible]

ATTACHMENT C

Survey Results

MONITORING WELL LOCATIONS

| WELL # | NORTHING | EASTING | ELEV' N |
|--------|-----------|------------|---------|
| MW1 | 652420.95 | 1501037.36 | 656.46 |
| MW2 | 652236.04 | 1501068.68 | 657.38 |
| MW3 | 651968.07 | 1501010.69 | 658.48 |
| MW4 | 652084.53 | 1501062.56 | 654.44 |
| MW5 | 652174.96 | 1501142.64 | 657.50 |
| MW6 | 652143.69 | 1500937.27 | 660.21 |


The horizontal coordinates were established by GPS observations and are referenced to NAD 83.

The elevations given are the orthometric height as determined by GPS observations and are referenced to NAVD 88.

NGS Monuments used in this survey:

PID - AE3350
& PID - AH3427

The tie from NGS monument AE3350 to MW1 is
N 58°27' 47" E 7982.28'




Note: This seal applies only to this document. I do not claim any responsibility for any other documents or instruments relating to or intended to be used for any part or parts of this project or any other project.

MONITORING WELLS
For PSARA Technologies, Inc.
Dayton Electroplating Site
Dayton, Montgomery County, Ohio

| |
|---------------|
| Drawn: GES |
| Checked: BLP |
| Date: 9/29/99 |
| Scale: N/A |
| Job No.: 3031 |

B. L. Payne & Associates, Inc.
Civil Engineers & Surveyors
11479 Colerain Avenue
Cincinnati, Ohio 45252
Phone: (513) 385-5922 Fax: (513) 385- 8103
bpayne@att.net



Rev. 12/8/99 - MW3 Elev.

ATTACHMENT D
IDW Analytical Results



Quanterra Incorporated
4101 Shuffel Drive, NW
North Canton, Ohio 44720

330 497-9396 Telephone
330 497-0772 Fax

ANALYTICAL REPORT

PROJECT NO. 60008.11

ORPA-SWDO MOB ORDER 557-09

Lot #: A9I020127

Rich Stuck

PSARA Technologies

QUANTERRA INCORPORATED

A handwritten signature in black ink, appearing to read "Jeffrey C. Smith".

Jeffrey C. Smith
Project Manager

October 1, 1999

CASE NARRATIVE

The following report contains the analytical results for four solid samples submitted to Quanterra-North Canton by PSARA Technologies from the OEPA-SWDO MOB Order 557-09 Site, project number 60008.11. The samples were received September 2, 1999, according to documented sample acceptance procedures.

Samples submitted for reactive cyanide and reactive sulfide analysis were received after the recommended holding times had been exceeded.

Quanterra-North Canton utilizes USEPA approved methods in all analytical work. The samples presented in this report were analyzed for the parameters listed on the method reference page in accordance with the methods indicated.

The results included in this report have been reviewed for compliance with the laboratory QA/QC plan. All data have been found to be compliant with laboratory protocol.

SUPPLEMENTAL QC INFORMATION

SAMPLE RECEIVING

The coolers were received at the laboratory at a temperature of 0.2° C.

GC/MS SEMIVOLATILES

The MS/MSDs performed on samples 8.11-001 MW-2 and 8.11-004 MW-6 had RPDs and/or recoveries outside acceptance limits. However, since the associated method blank and check were in control, no corrective action was necessary.

The MS/MSD performed on sample 8.11-003 MW-4&MW-5 had recoveries outside acceptance limits. Since the RPDs were in control, no corrective action was necessary.

Sample 8.11-003 MW-4&MW-5 had surrogate recoveries outside acceptance limits. Upon reextraction and reanalysis, the surrogates were again outside acceptance limits demonstrating a matrix effect.

ANALYTICAL METHODS SUMMARY

A9I020127

| PARAMETER | ANALYTICAL METHOD |
|--|----------------------|
| Chlorinated Herbicides by GC | SW846 8151A |
| Inductively Coupled Plasma (ICP) Metals | SW846 6010B |
| Mercury in Liquid Waste (Manual Cold-Vapor) | SW846 7470A |
| Organochlorine Pesticides | SW846 8081A |
| Pensky-Martens Method for Determining Ignitability | SW846 1010 |
| Reactive Cyanide | SW846 7.3.3 |
| Reactive Sulfide | SW846 7.3.4 |
| Semivolatile Organic Compounds by GC/MS | SW846 8270C |
| Soil and Waste pH | SW846 9045C |
| Volatile Organics by GC/MS | SW846 8260B |

References:

SW846 "Test Methods for Evaluating Solid Waste, Physical/Chemical Methods", Third Edition, November 1986 and its updates.

SAMPLE SUMMARY

A9I020127

| WO # | SAMPLE# | CLIENT SAMPLE ID | DATE | TIME |
|-------|---------|--------------------|----------|-------|
| D2252 | 001 | 8.11-001 MW-2 | 08/23/99 | 14:00 |
| D2256 | 002 | 8.11-002 MW-3 | 08/24/99 | 11:00 |
| D2257 | 003 | 8.11-003 MW-4&MW-5 | 08/25/99 | 17:00 |
| D225A | 004 | 8.11-004 MW-6 | 08/26/99 | 16:00 |

NOTE(S) :

- The analytical results of the samples listed above are presented on the following pages.
- All calculations are performed before rounding to avoid round-off errors in calculated results.
- Results noted as "ND" were not detected at or above the stated limit.
- This report must not be reproduced, except in full, without the written approval of the laboratory.
- Results for the following parameters are never reported on a dry weight basis: color, corrosivity, density, flashpoint, ignitability, layers, odor, paint filter test, pH, porosity pressure, reactivity, redox potential, specific gravity, spot tests, solids, solubility, temperature, viscosity, and weight.

PSARA TECHNOLOGIES

Client Sample ID: 8.11-001 MW-2

TCLP GC/MS Volatiles

Lot Sample #....: A9I020127-001 Work Order #....: D2252101 Matrix.....: SOLID
 Date Sampled...: 08/23/99 14:00 Date Received...: 09/02/99
 Leach Date.....: 09/03/99 Prep Date.....: 09/10/99 Analysis Date...: 09/10/99
 Leach Batch #...: P924508 Prep Batch #....: 9250138
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8260B

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|----------------------|--------|--------------------|-------|
| Benzene | ND | 0.025 | mg/L |
| Carbon tetrachloride | ND | 0.025 | mg/L |
| Chlorobenzene | ND | 0.025 | mg/L |
| Chloroform | ND | 0.025 | mg/L |
| 1,2-Dichloroethane | ND | 0.025 | mg/L |
| 1,1-Dichloroethylene | ND | 0.070 | mg/L |
| Methyl ethyl ketone | ND | 20 | mg/L |
| Tetrachloroethylene | ND | 0.070 | mg/L |
| Trichloroethylene | ND | 0.050 | mg/L |
| Vinyl chloride | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-----------------------|---------------------|--------------------|
| 1,2-Dichloroethane-d4 | 98 | (75 - 117) |
| Toluene d8 | 94 | (86 - 122) |
| Bromofluorobenzene | 91 | (60 - 137) |
| Dibromofluoromethane | 96 | (70 - 135) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-001 MW-2

TCLP GC/MS Semivolatiles

Lot-Sample #...: A9I020127-001 Work Order #...: D2252102 Matrix.....: SOLID
 Date Sampled...: 08/23/99 14:00 Date Received...: 09/02/99
 Leach Date.....: 09/04/99 Prep Date.....: 09/08/99 Analysis Date...: 09/13/99
 Leach Batch #...: P924701 Prep Batch #...: 9250215
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8270C

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| o-Cresol | ND | 0.050 | mg/L |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L |
| Hexachlorobenzene | ND | 0.050 | mg/L |
| Hexachlorobutadiene | ND | 0.050 | mg/L |
| Hexachloroethane | ND | 0.050 | mg/L |
| Nitrobenzene | ND | 0.050 | mg/L |
| Pentachlorophenol | ND | 0.10 | mg/L |
| Pyridine | ND | 0.10 | mg/L |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 84 | (44 - 110) |
| 2-Fluorobiphenyl | 84 | (50 - 105) |
| Terphenyl-d14 | 124 | (11 - 158) |
| Phenol-d5 | 51 | (10 - 131) |
| 2-Fluorophenol | 30 | (10 - 130) |
| 2,4,6-Tribromophenol | 84 | (10 - 156) |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-001 MW-2

TCLP GC Semivolatiles

Lot-Sample #....: A9I020127-001 Work Order #....: D2252103 Matrix.....: SOLID
 Date Sampled....: 08/23/99 14:00 Date Received...: 09/02/99
 Leach Date.....: 09/04/99 Prep Date.....: 09/08/99 Analysis Date...: 09/11/99
 Leach Batch #...: P924701 Prep Batch #....: 9250211
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8081A

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| Chlordane (technical) | ND | 0.0050 | mg/L |
| Endrin | ND | 0.00050 | mg/L |
| Heptachlor | ND | 0.00050 | mg/L |
| Heptachlor epoxide | ND | 0.00050 | mg/L |
| Lindane | ND | 0.00050 | mg/L |
| Methoxychlor | ND | 0.0010 | mg/L |
| Toxaphene | ND | 0.020 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 85 | (60 - 150) |
| Tetrachloro-m-xylene | 82 | (14 - 155) |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-001 MW-2

TCLP GC Semivolatiles

Lot-Sample #...: A9I020127-001 Work Order #...: D2252104 Matrix.....: SOLID
 Date Sampled...: 08/23/99 14:00 Date Received...: 09/02/99
 Leach Date.....: 09/04/99 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
 Leach Batch #...: P924701 Prep Batch #...: 9252314
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8151A

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-------------------|--------|--------------------|-------|
| 2,4-D | ND | 0.50 | mg/L |
| 2,4,5-TP (Silvex) | ND | 0.10 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-------------------------------|---------------------|--------------------|
| 2,4-Dichlorophenylacetic acid | 73 | (53 - 168) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-001 MW-2

TCLP Metals

Lot-Sample #....: A9I020127-001

Matrix.....: SOLID

Date Sampled....: 08/23/99 14:00 Date Received...: 09/02/99

Leach Date.....: 09/04/99 Leach Batch #...: P924701

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|---------------------------|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| Prep Batch #....: 9251209 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D2252105 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/09-09/15/99 | D2252106 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/09-09/15/99 | D2252107 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D2252108 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D2252109 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/09-09/15/99 | D225210A |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D225210C |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/09-09/10/99 | D225210D |
| | | Dilution Factor: 1 | | | | |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-001 MW-2

General Chemistry

Lot-Sample #....: A9I020127-001 Work Order #....: D2252 Matrix.....: SOLID
 Date Sampled....: 08/23/99 14:00 Date Received...: 09/02/99
 % Moisture.....:

| PARAMETER | RESULT | RL | UNITS | METHOD | PREPARATION- ANALYSIS DATE | PREP BATCH # |
|------------------|--------------------|-----|----------|-------------|-------------------------------|-----------------|
| pH (solid) | 8.6 | | No Units | SW846 9045C | 09/02/99 | 9252464 |
| | Dilution Factor: 1 | | | | | |
| Flashpoint | >180 | | deg F | SW846 1010 | 09/22/99 | 9265406 |
| | Dilution Factor: 1 | | | | | |
| Reactive Cyanide | ND | 200 | mg/kg | SW846 7.3.3 | 09/14-09/19/99 | 9262118 |
| | Dilution Factor: 1 | | | | | |
| Reactive Sulfide | ND | 200 | mg/kg | SW846 7.3.4 | 09/14-09/19/99 | 9262116 |
| | Dilution Factor: 1 | | | | | |

PSARA TECHNOLOGIES

Client Sample ID: 8.11-002 MW-3

TCLP GC/MS Volatiles

Lot-Sample #....: A9I020127-002 Work Order #....: D2256101 Matrix.....: SOLID
 Date Sampled...: 08/24/99 11:00 Date Received...: 09/02/99
 Leach Date.....: 09/03/99 Prep Date.....: 09/10/99 Analysis Date...: 09/10/99
 Leach Batch #...: P924508 Prep Batch #....: 9250138
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8260B

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|----------------------|--------|--------------------|-------|
| Benzene | ND | 0.025 | mg/L |
| Carbon tetrachloride | ND | 0.025 | mg/L |
| Chlorobenzene | ND | 0.025 | mg/L |
| Chloroform | ND | 0.025 | mg/L |
| 1,2-Dichloroethane | ND | 0.025 | mg/L |
| 1,1-Dichloroethylene | ND | 0.070 | mg/L |
| Methyl ethyl ketone | ND | 20 | mg/L |
| Tetrachloroethylene | ND | 0.070 | mg/L |
| Trichloroethylene | ND | 0.050 | mg/L |
| Vinyl chloride | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-----------------------|---------------------|--------------------|
| 1,2-Dichloroethane-d4 | 94 | (75 - 117) |
| Toluene-d8 | 96 | (86 - 122) |
| Bromofluorobenzene | 90 | (60 - 137) |
| Dibromofluoromethane | 96 | (70 - 135) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-002 MW-3

TCLP GC/MS Semivolatiles

Lot-Sample #....: A9I020127-002 Work Order #....: D2256102 Matrix.....: SOLID
 Date Sampled....: 08/24/99 11:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251149
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8270C

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| o-Cresol | ND | 0.050 | mg/L |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L |
| Hexachlorobenzene | ND | 0.050 | mg/L |
| Hexachlorobutadiene | ND | 0.050 | mg/L |
| Hexachloroethane | ND | 0.050 | mg/L |
| Nitrobenzene | ND | 0.050 | mg/L |
| Pentachlorophenol | ND | 0.10 | mg/L |
| Pyridine | ND | 0.10 | mg/L |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 72 | (44 - 110) |
| 2-Fluorobiphenyl | 71 | (50 - 105) |
| Terphenyl-d14 | 120 | (11 - 158) |
| Phenol-d5 | 32 | (10 - 131) |
| 2-Fluorophenol | 12 | (10 - 130) |
| 2,4,6-Tribromophenol | 65 | (10 - 156) |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-002 MW-3

TCLP GC Semivolatiles

Lot-Sample #....: A9I020127-002 Work Order #....: D2256103 Matrix.....: SOLID
 Date Sampled....: 08/24/99 11:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251148
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8081A

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| Chlordane (technical) | ND | 0.0050 | mg/L |
| Endrin | ND | 0.00050 | mg/L |
| Heptachlor | ND | 0.00050 | mg/L |
| Heptachlor epoxide | ND | 0.00050 | mg/L |
| Lindane | ND | 0.00050 | mg/L |
| Methoxychlor | ND | 0.0010 | mg/L |
| Toxaphene | ND | 0.020 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 59 * | (60 - 150) |
| Tetrachloro-m-xylene | 77 | (14 - 155) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

- * Surrogate recovery is outside stated control limits.

PSARA TECHNOLOGIES

Client Sample ID: 8.11-002 MW-3

TCLP GC Semivolatiles

Lot-Sample #....: A9I020127-002 Work Order #....: D2256104 Matrix.....: SOLID
Date Sampled....: 08/24/99 11:00 Date Received...: 09/02/99
Leach Date.....: 09/08/99 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
Leach Batch #...: P925102 Prep Batch #....: 9252316
Dilution Factor: 1
% Moisture.....: Method.....: SW846 8151A

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-------------------|--------|--------------------|-------|
| 2,4-D | ND | 0.50 | mg/L |
| 2,4,5-TP (Silvex) | ND | 0.10 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-------------------------------|---------------------|--------------------|
| 2,4-Dichlorophenylacetic acid | 63 | (53 - 168) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-002 MW-3

TCLP Metals

Lot-Sample #....: A9I020127-002

Matrix.....: SOLID

Date Sampled....: 08/24/99 11:00 Date Received...: 09/02/99

Leach Date.....: 09/08/99 Leach Batch #...: P925102

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|---------------------------|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| Prep Batch #....: 9252299 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2256105 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/10-09/15/99 | D2256106 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/10-09/15/99 | D2256107 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2256108 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2256109 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/10-09/15/99 | D225610A |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D225610C |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/10-09/11/99 | D225610D |
| | | Dilution Factor: 1 | | | | |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-002 MW-3

General Chemistry

Lot-Sample #....: A9I020127-002 Work Order #....: D2256 Matrix.....: SOLID
 Date Sampled....: 08/24/99 11:00 Date Received...: 09/02/99
 % Moisture.....:

| PARAMETER | RESULT | RL | UNITS | METHOD | PREPARATION- ANALYSIS DATE | PREP BATCH # |
|------------------|----------------------------|-----|----------|-------------|-------------------------------|-----------------|
| pH (solid) | 8.8 Dilution Factor: 1 | | No Units | SW846 9045C | 09/02/99 | 9252464 |
| Flashpoint | >180 Dilution Factor: 1 | | deg F | SW846 1010 | 09/22/99 | 9265406 |
| Reactive Cyanide | ND Dilution Factor: 1 | 200 | mg/kg | SW846 7.3.3 | 09/14-09/19/99 | 9262118 |
| Reactive Sulfide | ND Dilution Factor: 1 | 200 | mg/kg | SW846 7.3.4 | 09/14-09/19/99 | 9262116 |

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

TCLP GC/MS Volatiles

Lot-Sample #....: A9I020127-003 Work Order #....: D2257101 Matrix.....: SOLID
 Date Sampled....: 08/25/99 17:00 Date Received...: 09/02/99
 Leach Date.....: 09/03/99 Prep Date.....: 09/10/99 Analysis Date...: 09/10/99
 Leach Batch #...: P924508 Prep Batch #....: 9250138
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8260B

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|----------------------|--------|--------------------|-------|
| Benzene | ND | 0.025 | mg/L |
| Carbon tetrachloride | ND | 0.025 | mg/L |
| Chlorobenzene | ND | 0.025 | mg/L |
| Chloroform | ND | 0.025 | mg/L |
| 1,2-Dichloroethane | ND | 0.025 | mg/L |
| 1,1-Dichloroethylene | ND | 0.070 | mg/L |
| Methyl ethyl ketone | ND | 20 | mg/L |
| Tetrachloroethylene | ND | 0.070 | mg/L |
| Trichloroethylene | ND | 0.050 | mg/L |
| Vinyl chloride | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-----------------------|---------------------|--------------------|
| 1,2-Dichloroethane-d4 | 98 | (75 - 117) |
| Toluene-d8 | 94 | (86 - 122) |
| Bromofluorobenzene | 90 | (60 - 137) |
| Dibromofluoromethane | 97 | (70 - 135) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

TCLP GC/MS Semivolatiles

Lot-Sample #....: A9I020127-003 Work Order #....: D2257102 Matrix.....: SOLID
 Date Sampled....: 08/25/99 17:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251149
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8270C

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| o-Cresol | ND | 0.050 | mg/L |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L |
| Hexachlorobenzene | ND | 0.050 | mg/L |
| Hexachlorobutadiene | ND | 0.050 | mg/L |
| Hexachloroethane | ND | 0.050 | mg/L |
| Nitrobenzene | ND | 0.050 | mg/L |
| Pentachlorophenol | ND | 0.10 | mg/L |
| Pyridine | ND | 0.10 | mg/L |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 72 | (44 - 110) |
| 2-Fluorobiphenyl | 73 | (50 - 105) |
| Terphenyl-d14 | 131 | (11 - 158) |
| Phenol-d5 | 4.8 * | (10 - 131) |
| 2-Fluorophenol | 0.0 * | (10 - 130) |
| 2,4,6-Tribromophenol | 34 | (10 - 156) |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

- * Surrogate recovery is outside stated control limits.

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

TCLP GC/MS Semivolatiles

Lot Sample #....: A9I020127-003 Work Order #....: D2257202 Matrix.....: SOLID
 Date Sampled....: 08/25/99 17:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/18/99 Analysis Date...: 09/22/99
 Leach Batch #...: P925102 Prep Batch #....: 9261107
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8270C

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| o-Cresol | ND | 0.050 | mg/L |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L |
| Hexachlorobenzene | ND | 0.050 | mg/L |
| Hexachlorobutadiene | ND | 0.050 | mg/L |
| Hexachloroethane | ND | 0.050 | mg/L |
| Nitrobenzene | ND | 0.050 | mg/L |
| Pentachlorophenol | ND | 0.10 | mg/L |
| Pyridine | ND | 0.10 | mg/L |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 64 | (44 - 110) |
| 2-Fluorobiphenyl | 55 | (50 - 105) |
| Terphenyl-d14 | 68 | (11 - 158) |
| Phenol-d5 | 0.0 * | (10 - 131) |
| 2-Fluorophenol | 0.0 * | (10 - 130) |
| 2,4,6-Tribromophenol | 26 | (10 - 156) |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

- * Surrogate recovery is outside stated control limits.

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

TCLP GC Semivolatiles

Lot-Sample #....: A9I020127-003 Work Order #....: D2257103 Matrix.....: SOLID
 Date Sampled...: 08/25/99 17:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251148
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8081A

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| Chlordane (technical) | ND | 0.0050 | mg/L |
| Endrin | ND | 0.00050 | mg/L |
| Heptachlor | ND | 0.00050 | mg/L |
| Heptachlor epoxide | ND | 0.00050 | mg/L |
| Lindane | ND | 0.00050 | mg/L |
| Methoxychlor | ND | 0.0010 | mg/L |
| Toxaphene | ND | 0.020 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 81 | (60 - 150) |
| Tetrachloro-m-xylene | 84 | (14 - 155) |

NOTE(S):

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

TCLP GC Semivolatiles

Lot-Sample #...: A9I020127-003 Work Order #...: D2257104 Matrix.....: SOLID
Date Sampled...: 08/25/99 17:00 Date Received...: 09/02/99
Leach Date.....: 09/08/99 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
Leach Batch #...: P925102 Prep Batch #...: 9252316
Dilution Factor: 1
% Moisture.....: Method.....: SW846 8151A

| <u>PARAMETER</u> | <u>RESULT</u> | <u>REPORTING LIMIT</u> | <u>UNITS</u> |
|-------------------|---------------|----------------------------|--------------|
| 2,4-D | ND | 0.50 | mg/L |
| 2,4,5-TP (Silvex) | ND | 0.10 | mg/L |

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|-------------------------------|-----------------------------|----------------------------|
| 2,4-Dichlorophenylacetic acid | 70 | (53 - 168) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

TCLP Metals

Lot-Sample #...: A9I020127-003

Matrix.....: SOLID

Date Sampled...: 08/25/99 17:00 Date Received...: 09/02/99

Leach Date.....: 09/08/99 Leach Batch #...: P925102

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|--------------------------|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| Prep Batch #...: 9252299 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2257105 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/10-09/15/99 | D2257106 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/10-09/15/99 | D2257107 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2257108 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2257109 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/10-09/15/99 | D225710A |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D225710C |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/10-09/11/99 | D225710D |
| | | Dilution Factor: 1 | | | | |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-003 MW-4&MW-5

General Chemistry

Lot-Sample #....: A9I020127-003 Work Order #....: D2257 Matrix.....: SOLID
 Date Sampled....: 08/25/99 17:00 Date Received...: 09/02/99
 % Moisture.....:

| PARAMETER | RESULT | RL | UNITS | METHOD | PREPARATION- ANALYSIS DATE | PREP BATCH # |
|------------------|--------------------|-----|----------|-------------|-------------------------------|-----------------|
| pH (solid) | 8.9 | | No Units | SW846 9045C | 09/02/99 | 9252464 |
| | Dilution Factor: 1 | | | | | |
| Flashpoint | >180 | | deg F | SW846 1010 | 09/22/99 | 9265406 |
| | Dilution Factor: 1 | | | | | |
| Reactive Cyanide | ND | 200 | mg/kg | SW846 7.3.3 | 09/14-09/19/99 | 9262118 |
| | Dilution Factor: 1 | | | | | |
| Reactive Sulfide | ND | 200 | mg/kg | SW846 7.3.4 | 09/14-09/19/99 | 9262116 |
| | Dilution Factor: 1 | | | | | |

PSARA TECHNOLOGIES

Client Sample ID: 8.11-004 MW-6

TCLP GC/MS Volatiles

Lot Sample #....: A9I020127-004 Work Order #....: D225A101 Matrix.....: SOLID
 Date Sampled....: 08/26/99 16:00 Date Received...: 09/02/99
 Leach Date.....: 09/03/99 Prep Date.....: 09/10/99 Analysis Date...: 09/10/99
 Leach Batch #...: P924508 Prep Batch #....: 9250138
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8260B

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|----------------------|--------|--------------------|-------|
| Benzene | ND | 0.025 | mg/L |
| Carbon tetrachloride | ND | 0.025 | mg/L |
| Chlorobenzene | ND | 0.025 | mg/L |
| Chloroform | ND | 0.025 | mg/L |
| 1,2-Dichloroethane | ND | 0.025 | mg/L |
| 1,1-Dichloroethylene | ND | 0.070 | mg/L |
| Methyl ethyl ketone | ND | 20 | mg/L |
| Tetrachloroethylene | ND | 0.070 | mg/L |
| Trichloroethylene | ND | 0.050 | mg/L |
| Vinyl chloride | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-----------------------|---------------------|--------------------|
| 1,2-Dichloroethane-d4 | 97 | (75 - 117) |
| Toluene-d8 | 95 | (86 - 122) |
| Bromofluorobenzene | 91 | (60 - 137) |
| Dibromofluoromethane | 96 | (70 - 135) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-004 MW-6

TCLP GC/MS Semivolatiles

Lot-Sample #....: A9I020127-004 Work Order #....: D225A102 Matrix.....: SOLID
 Date Sampled....: 08/26/99 16:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251149
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8270C

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| o-Cresol | ND | 0.050 | mg/L |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L |
| Hexachlorobenzene | ND | 0.050 | mg/L |
| Hexachlorobutadiene | ND | 0.050 | mg/L |
| Hexachloroethane | ND | 0.050 | mg/L |
| Nitrobenzene | ND | 0.050 | mg/L |
| Pentachlorophenol | ND | 0.10 | mg/L |
| Pyridine | ND | 0.10 | mg/L |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 68 | (44 - 110) |
| 2-Fluorobiphenyl | 66 | (50 - 105) |
| Terphenyl-d14 | 127 | (11 - 158) |
| Phenol-d5 | 34 | (10 - 131) |
| 2-Fluorophenol | 13 | (10 - 130) |
| 2,4,6-Tribromophenol | 62 | (10 - 156) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-004 MW-6

TCLP GC Semivolatiles

Lot-Sample #....: A9I020127-004 Work Order #....: D225A103 Matrix.....: SOLID
 Date Sampled....: 08/26/99 16:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251148
 Dilution Factor: 1
 % Moisture.....: Method.....: SW846 8081A

| PARAMETER | RESULT | REPORTING LIMIT | UNITS |
|-----------------------|--------|--------------------|-------|
| Chlordane (technical) | ND | 0.0050 | mg/L |
| Endrin | ND | 0.00050 | mg/L |
| Heptachlor | ND | 0.00050 | mg/L |
| Heptachlor epoxide | ND | 0.00050 | mg/L |
| Lindane | ND | 0.00050 | mg/L |
| Methoxychlor | ND | 0.0010 | mg/L |
| Toxaphene | ND | 0.020 | mg/L |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 81 | (60 - 150) |
| Tetrachloro-m-xylene | 74 | (14 - 155) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-004 MW-6

TCLP GC Semivolatiles

Lot-Sample #...: A9I020127-004 Work Order #...: D225A104 Matrix.....: SOLID
Date Sampled...: 08/26/99 16:00 Date Received...: 09/02/99
Leach Date.....: 09/08/99 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
Leach Batch #...: P925102 Prep Batch #...: 9252316
Dilution Factor: 1
% Moisture.....: Method.....: SW846 8151A

| <u>PARAMETER</u> | <u>RESULT</u> | <u>REPORTING LIMIT</u> | <u>UNITS</u> |
|-------------------|---------------|----------------------------|--------------|
| 2,4-D | ND | 0.50 | mg/L |
| 2,4,5-TP (Silvex) | ND | 0.10 | mg/L |

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|-------------------------------|-----------------------------|----------------------------|
| 2,4-Dichlorophenylacetic acid | 79 | (53 - 168) |

NOTE(S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-004 MW-6

TCLP Metals

Lot-Sample #....: A9I020127-004

Matrix.....: SOLID

Date Sampled...: 08/26/99 16:00 Date Received...: 09/02/99

Leach Date.....: 09/08/99 Leach Batch #...: P925102

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|---------------------------|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| Prep Batch #....: 9252299 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A105 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A106 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A107 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A108 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A109 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A10A |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D225A10C |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/10-09/11/99 | D225A10D |
| | | Dilution Factor: 1 | | | | |

NOTES (S) :

Analysis performed in accordance with USEPA Toxicity Characteristic Leaching Procedure Method 1311 (55 FR 26986)

PSARA TECHNOLOGIES

Client Sample ID: 8.11-004 MW-6

General Chemistry

Lot-Sample #....: A9I020127-004 Work Order #....: D225A Matrix.....: SOLID
 Date Sampled....: 08/26/99 16:00 Date Received...: 09/02/99
 % Moisture.....:

| PARAMETER | RESULT | RL | UNITS | METHOD | PREPARATION- ANALYSIS DATE | PREP BATCH # |
|------------------|--------------------|-----|----------|-------------|-------------------------------|-----------------|
| pH (solid) | 9.0 | | No Units | SW846 9045C | 09/02/99 | 9252464 |
| | Dilution Factor: 1 | | | | | |
| Flashpoint | >180 | | deg F | SW846 1010 | 09/22/99 | 9265406 |
| | Dilution Factor: 1 | | | | | |
| Reactive Cyanide | ND | 200 | mg/kg | SW846 7.3.3 | 09/14-09/19/99 | 9262118 |
| | Dilution Factor: 1 | | | | | |
| Reactive Sulfide | ND | 200 | mg/kg | SW846 7.3.4 | 09/14-09/19/99 | 9262116 |
| | Dilution Factor: 1 | | | | | |

QUALITY CONTROL SECTION

QUALITY CONTROL ELEMENTS OF SW-846 METHODS

Quanterra[®] Incorporated conducts a quality assurance/quality control (QA/QC) program designed to provide scientifically valid and legally defensible data. Toward this end, several types of quality control indicators are incorporated into the QA/QC program. These indicators are introduced into the sample testing process to provide a mechanism for the assessment of the analytical data.

QC BATCH

Environmental samples are taken through the testing process in groups called QUALITY CONTROL BATCHES (QC batches). A QC batch contains up to twenty environmental samples of a similar matrix (water, soil) that are processed using the same reagents and standards. Quanterra requires that each environmental sample be associated with a QC batch.

Several quality control samples are included in each QC batch and are processed identically to the twenty environmental samples. These QC samples include a METHOD BLANK (MB), a LABORATORY CONTROL SAMPLE (LCS) and, where appropriate, a MATRIX SPIKE/MATRIX SPIKE DUPLICATE (MS/MSD) pair or a MATRIX SPIKE/SAMPLE DUPLICATE (MS/DU) pair. If there is insufficient sample to perform an MS/MSD or an MS/DU, then a LABORATORY CONTROL SAMPLE DUPLICATE (LCSD) is included in the QC batch.

LABORATORY CONTROL SAMPLE

The Laboratory Control Sample is a QC sample that is created by adding known concentrations of a full or partial set of target analytes to a matrix similar to that of the environmental samples in the QC batch. The LCS analyte recovery results are used to monitor the analytical process and provide evidence that the laboratory is performing the method within acceptable guidelines. Failure to meet the established recovery guidelines requires the reparation and reanalysis of all samples in the QC batch. The only exception is that if the LCS recoveries are biased high and the associated sample is ND for the parameter(s) of interest, the batch is acceptable.

At times, a Laboratory Control Sample Duplicate (LCSD) is also included in the QC batch. An LCSD is a QC sample that is created and handled identically to the LCS. Analyte recovery data from the LCSD is assessed in the same way as that of the LCS. The LCSD recoveries, together with the LCS recoveries, are used to determine the reproducibility (precision) of the analytical system. Precision data are expressed as relative percent differences (RPDs). Failure of the RPDs to fall within the laboratory-generated acceptance windows requires the reparation and reanalysis of all samples in the QC batch. The only exception is that if the MS/MSD RPDs are within acceptance criteria, the batch is acceptable.

METHOD BLANK

The Method Blank is a QC sample consisting of all the reagents used in analyzing the environmental samples contained in the QC batch. Method Blank results are used to determine if interference or contamination in the analytical system could lead to the reporting of false positive data or elevated analyte concentrations. All target analytes must be below the reporting limits (RL) or the associated sample(s) must be ND except for the common laboratory contaminants indicated below.

Volatile (GC or GC/MS)

Methylene chloride
Acetone
2-Butanone

Semivolatile (GC/MS)

Phthalate Esters

Metals

Copper
Iron
Zinc
Lead*

* for analyses run on TJA Trace ICP or GFAA only

QUALITY CONTROL ELEMENTS OF SW-846 METHODS (Continued)

The listed volatile and semivolatile compounds may be present in concentrations up to 5 times the reporting limits. The listed metals may be present in concentrations up to 2 times the reporting limit or must be twenty fold less than the results of the environmental samples. Failure to meet these Method Blank criteria requires the reparation and reanalysis of all samples in the QC batch.

MATRIX SPIKE/MATRIX SPIKE DUPLICATE

A Matrix Spike and a Matrix Spike Duplicate are a pair of environmental samples to which known concentrations of a full or partial set of target analytes are added. The MS/MSD results are determined in the same manner as the results of the environmental sample used to prepare the MS/MSD. The analyte recoveries and the relative percent differences (RPDs) of the recoveries are calculated and used to evaluate the effect of the sample matrix on the analytical results. When these values fail to meet acceptance criteria, the data is reviewed to determine the cause. If, in the analyst's judgment, sample matrix effects are indicated, no corrective action is performed. Otherwise, the MS/MSD and the environmental sample used to prepare them are reprepared and reanalyzed.

For certain methods, a Matrix Spike/Sample Duplicate (MS/DU) may be included in the QC batch in place of the MS/MSD. For the parameters (i.e. pH, ignitability) where it is not possible to prepare a spiked sample, a Sample Duplicate may be included in the QC batch.

SURROGATE COMPOUNDS

In addition to these batch-related QC indicators, each organic environmental and QC sample are spiked with surrogate compounds. Surrogates are organic chemicals that behave similarly to the analytes of interest and that are rarely present in the environment. Surrogate recoveries are used to monitor the individual performance of a sample in the analytical system.

The acceptance criteria do not apply to samples that are diluted. All other surrogate recoveries will be reported. If the LCS, LCSD, or the Method Blank surrogates fail to meet recovery criteria (exception for dilutions), the entire batch of samples is reprepared and reanalyzed.

If the surrogate recoveries are biased high in the LCS, LCSD, or the Method Blank and the associated sample(s) are ND, the batch is acceptable. If the surrogate recoveries are outside criteria for environmental or MS/MSD samples, the batch may be acceptable based on the analyst's judgment that sample matrix effects are indicated.

For the GC/MS BNA methods, the surrogate criteria is that two of the three surrogates for each fraction must meet acceptance criteria. The third surrogate must have a recovery of ten percent or greater.

For the Pesticide/PCB, PAH, TPH, and Herbicide methods, the surrogate criteria is that one of two surrogate compounds meet acceptance criteria.

Quanterra Incorporated – North Canton Facility, Certifications and Approvals:

Alabama (#41170), California (#2157), Connecticut (#PII-0590), Florida (#E87225) – Florida CompQAPP (#890651G), Kentucky (#90021), Massachusetts (#M-OH048), Maryland (#272), Minnesota (#39-999-348), Missouri (#6090), New Jersey (#74001), New York (#10975), North Dakota (#R-156), Ohio (#6090), OhioVAP (#C1.0024), Pennsylvania (#68-340), South Carolina (#92007001, #92007002, #92007003), Tennessee (#02903), West Virginia (#210), Wisconsin (#999518190), NAVY, ARMY, USDA Soil Permit

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Volatiles

Client Lot #....: A9I020127 Work Order #....: D25PM102 Matrix.....: SOLID
 LCS Lot-Sample#: A9I070000-138
 Prep Date.....: 09/07/99 Analysis Date...: 09/07/99
 Prep Batch #....: 9250138
 Dilution Factor: 1

| <u>PARAMETER</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> | <u>METHOD</u> |
|----------------------|-----------------------------|----------------------------|---------------|
| 1,1-Dichloroethylene | 109 | (76 - 128) | SW846 8260B |
| Trichloroethylene | 95 | (86 - 116) | SW846 8260B |
| Chlorobenzene | 103 | (88 - 119) | SW846 8260B |
| Benzene | 108 | (85 - 120) | SW846 8260B |
| Toluene | 105 | (86 - 118) | SW846 8260B |

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|-----------------------|-----------------------------|----------------------------|
| 1,2-Dichloroethane-d4 | 93 | (75 - 117) |
| Toluene-d8 | 101 | (86 - 122) |
| Bromofluorobenzene | 96 | (60 - 137) |
| Dibromofluoromethane | 99 | (70 - 135) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D2LL7102 Matrix.....: SOLID
 LCS Lot-Sample#: A9I180000-107
 Prep Date.....: 09/18/99 Analysis Date...: 09/22/99
 Prep Batch #....: 9261107
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | METHOD |
|-----------------------|---------------------|--------------------|-------------|
| 1,4-Dichlorobenzene | 62 | (34 - 113) | SW846 8270C |
| 2,4-Dinitrotoluene | 62 | (41 - 154) | SW846 8270C |
| Hexachlorobenzene | 86 | (57 - 118) | SW846 8270C |
| Hexachlorobutadiene | 71 | (44 - 104) | SW846 8270C |
| Hexachloroethane | 62 | (39 - 96) | SW846 8270C |
| Nitrobenzene | 74 | (49 - 111) | SW846 8270C |
| Pentachlorophenol | 31 | (24 - 145) | SW846 8270C |
| Pyridine | 49 | (5.0- 99) | SW846 8270C |
| 2,4,5-Trichlorophenol | 62 | (43 - 118) | SW846 8270C |
| 2,4,6-Trichlorophenol | 65 | (45 - 102) | SW846 8270C |
| o-Cresol | 65 | (46 - 109) | SW846 8270C |
| m-Cresol & p-Cresol | 62 | (46 - 109) | SW846 8270C |
| Cresols (total) | 63 | (46 - 109) | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 74 | (44 - 110) |
| 2-Fluorobiphenyl | 66 | (50 - 105) |
| Terphenyl-d14 | 90 | (11 - 158) |
| Phenol-d5 | 54 | (10 - 131) |
| 2-Fluorophenol | 66 | (10 - 130) |
| 2,4,6-Tribromophenol | 76 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D26JP102 Matrix.....: SOLID
 LCS Lot-Sample#: A9I080000-149
 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Prep Batch #....: 9251149
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | METHOD |
|-----------------------|---------------------|--------------------|-------------|
| 1,4-Dichlorobenzene | 60 | (34 - 113) | SW846 8270C |
| 2,4-Dinitrotoluene | 68 | (41 - 154) | SW846 8270C |
| Hexachlorobenzene | 90 | (57 - 118) | SW846 8270C |
| Hexachlorobutadiene | 66 | (44 - 104) | SW846 8270C |
| Hexachloroethane | 56 | (39 - 96) | SW846 8270C |
| Nitrobenzene | 74 | (49 - 111) | SW846 8270C |
| Pentachlorophenol | 30 | (24 - 145) | SW846 8270C |
| Pyridine | 55 | (5.0 - 99) | SW846 8270C |
| 2,4,5-Trichlorophenol | 57 | (43 - 118) | SW846 8270C |
| 2,4,6-Trichlorophenol | 61 | (45 - 102) | SW846 8270C |
| o-Cresol | 57 | (46 - 109) | SW846 8270C |
| m-Cresol & p-Cresol | 56 | (46 - 109) | SW846 8270C |
| Cresols (total) | 56 | (46 - 109) | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 72 | (44 - 110) |
| 2-Fluorobiphenyl | 71 | (50 - 105) |
| Terphenyl-d14 | 117 | (11 - 158) |
| Phenol-d5 | 42 | (10 - 131) |
| 2-Fluorophenol | 23 | (10 - 130) |
| 2,4,6-Tribromophenol | 71 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D2615102 Matrix.....: SOLID
 LCS Lot-Sample#: A9I070000-215
 Prep Date.....: 09/08/99 Analysis Date...: 09/13/99
 Prep Batch #...: 9250215
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | METHOD |
|-----------------------|---------------------|--------------------|-------------|
| o-Cresol | 73 | (46 - 109) | SW846 8270C |
| m-Cresol & p-Cresol | 72 | (46 - 109) | SW846 8270C |
| 1,4-Dichlorobenzene | 64 | (34 - 113) | SW846 8270C |
| 2,4-Dinitrotoluene | 77 | (41 - 154) | SW846 8270C |
| Hexachlorobenzene | 88 | (57 - 118) | SW846 8270C |
| Hexachlorobutadiene | 64 | (44 - 104) | SW846 8270C |
| Hexachloroethane | 61 | (39 - 96) | SW846 8270C |
| Nitrobenzene | 77 | (49 - 111) | SW846 8270C |
| Pentachlorophenol | 71 | (24 - 145) | SW846 8270C |
| Pyridine | 47 | (5.0 - 99) | SW846 8270C |
| 2,4,5-Trichlorophenol | 74 | (43 - 118) | SW846 8270C |
| 2,4,6-Trichlorophenol | 72 | (45 - 102) | SW846 8270C |
| Cresols (total) | 73 | (46 - 109) | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| 2,4,6-Tribromophenol | 85 | (10 - 156) |
| Nitrobenzene-d5 | 75 | (44 - 110) |
| 2-Fluorobiphenyl | 75 | (50 - 105) |
| Terphenyl-d14 | 100 | (11 - 158) |
| Phenol-d5 | 58 | (10 - 131) |
| 2-Fluorophenol | 31 | (10 - 130) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D26JN102-LCS Matrix.....: SOLID
 LCS Lot-Sample#: A9I080000-148 D26JN103-LCSD
 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Prep Batch #...: 9251148
 Dilution Factor: 5

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|--------------------|---------------------|--------------------|-----|---------------|-------------|
| Lindane | 96 | (50 - 150) | | | SW846 8081A |
| | 82 | (50 - 150) | 15 | (0-50) | SW846 8081A |
| Heptachlor | 96 | (50 - 150) | | | SW846 8081A |
| | 87 | (50 - 150) | 9.8 | (0-50) | SW846 8081A |
| Heptachlor epoxide | 93 | (50 - 150) | | | SW846 8081A |
| | 84 | (50 - 150) | 9.8 | (0-50) | SW846 8081A |
| Endrin | 107 | (50 - 150) | | | SW846 8081A |
| | 99 | (50 - 150) | 7.6 | (0-50) | SW846 8081A |
| Methoxychlor | 99 | (50 - 150) | | | SW846 8081A |
| | 88 | (50 - 150) | 12 | (0-50) | SW846 8081A |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 101 | (60 - 150) |
| | 91 | (60 - 150) |
| Tetrachloro-m-xylene | 92 | (14 - 155) |
| | 78 | (14 - 155) |

NOTE (S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D260K102-LCS Matrix.....: SOLID
 LCS Lot-Sample#: A9I070000-211 D260K103-LCSD
 Prep Date.....: 09/08/99 Analysis Date...: 09/11/99
 Prep Batch #....: 9250211
 Dilution Factor: 5

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|--------------------|---------------------|--------------------|-----|---------------|-------------|
| Lindane | 69 | (50 - 150) | | | SW846 8081A |
| | 73 | (50 - 150) | 5.6 | (0-50) | SW846 8081A |
| Heptachlor | 72 | (50 - 150) | | | SW846 8081A |
| | 78 | (50 - 150) | 6.7 | (0-50) | SW846 8081A |
| Heptachlor epoxide | 75 | (50 - 150) | | | SW846 8081A |
| | 81 | (50 - 150) | 7.7 | (0-50) | SW846 8081A |
| Endrin | 89 | (50 - 150) | | | SW846 8081A |
| | 96 | (50 - 150) | 8.1 | (0-50) | SW846 8081A |
| Methoxychlor | 156 a | (50 - 150) | | | SW846 8081A |
| | 118 | (50 - 150) | 28 | (0-50) | SW846 8081A |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 82 | (60 - 150) |
| | 86 | (60 - 150) |
| Tetrachloro-m-xylene | 72 | (14 - 155) |
| | 75 | (14 - 155) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results

Bold print denotes control parameters

a Spiked analyte recovery is outside stated control limits.

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D28WL102 Matrix.....: SOLID
 LCS Lot-Sample#: A9I090000-314
 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
 Prep Batch #....: 9252314
 Dilution Factor: 1

| <u>PARAMETER</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> | <u>METHOD</u> |
|-------------------|-----------------------------|----------------------------|---------------|
| 2,4-D | 78 | (58 - 132) | SW846 8151A |
| 2,4,5-TP (Silvex) | 72 | (25 - 122) | SW846 8151A |

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|-------------------------------|-----------------------------|----------------------------|
| 2,4-Dichlorophenylacetic acid | 83 | (53 - 168) |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

GC Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D28WT102 Matrix.....: SOLID
 LCS Lot-Sample#: A9I090000-316
 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
 Prep Batch #....: 9252316
 Dilution Factor: 1

| <u>PARAMETER</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> | <u>METHOD</u> |
|-------------------|-----------------------------|----------------------------|---------------|
| 2,4-D | 79 | (58 - 132) | SW846 8151A |
| 2,4,5-TP (Silvex) | 75 | (25 - 122) | SW846 8151A |

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|----------------------------------|-----------------------------|----------------------------|
| 2,4-Dichlorophenylacetic acid | 70 | (53 - 168) |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

LABORATORY CONTROL SAMPLE EVALUATION REPORT

TCLP Metals

Client Lot #....: A9I020127

Matrix.....: SOLID

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|-----------|---------------------|--------------------|--------|-------------------------------|--------------|
|-----------|---------------------|--------------------|--------|-------------------------------|--------------|

LCS Lot-Sample#: A9I080000-209 Prep Batch #....: 9251209

| | | | | | |
|--------|-----|--------------------|-------------|----------------|----------|
| Silver | 111 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV10A |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|---------|----|--------------------|-------------|----------------|----------|
| Mercury | 91 | (50 - 150) | SW846 7470A | 09/09-09/10/99 | D26QV10C |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|---------|-----|--------------------|-------------|----------------|----------|
| Arsenic | 104 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV10D |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|--------|-----|--------------------|-------------|----------------|----------|
| Barium | 103 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV10E |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|---------|-----|--------------------|-------------|----------------|----------|
| Cadmium | 106 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV10F |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|----------|-----|--------------------|-------------|----------------|----------|
| Chromium | 110 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV10G |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|------|-----|--------------------|-------------|----------------|----------|
| Lead | 104 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV10H |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|----------|-----|--------------------|-------------|----------------|----------|
| Selenium | 103 | (50 - 150) | SW846 6010B | 09/09-09/15/99 | D26QV109 |
| | | Dilution Factor: 1 | | | |

LCS Lot-Sample#: A9I090000-299 Prep Batch #....: 9252299

| | | | | | |
|--------|-----|--------------------|-------------|----------------|----------|
| Silver | 105 | (50 - 150) | SW846 6010B | 09/10-09/15/99 | D28PE10A |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|---------|----|--------------------|-------------|----------------|----------|
| Mercury | 95 | (50 - 150) | SW846 7470A | 09/10-09/11/99 | D28PE10C |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|---------|-----|--------------------|-------------|----------------|----------|
| Arsenic | 100 | (50 - 150) | SW846 6010B | 09/10-09/15/99 | D28PE10D |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|--------|----|--------------------|-------------|----------------|----------|
| Barium | 99 | (50 - 150) | SW846 6010B | 09/10-09/15/99 | D28PE10E |
| | | Dilution Factor: 1 | | | |

| | | | | | |
|---------|-----|--------------------|-------------|----------------|----------|
| Cadmium | 106 | (50 - 150) | SW846 6010B | 09/10-09/15/99 | D28PE10F |
| | | Dilution Factor: 1 | | | |

(Continued on next page)

LABORATORY CONTROL SAMPLE EVALUATION REPORT

TCLP Metals

Client Lot #....: A9I020127

Matrix.....: SOLID

| <u>PARAMETER</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> | <u>METHOD</u> | <u>PREPARATION- ANALYSIS DATE</u> | <u>WORK ORDER #</u> |
|------------------|-----------------------------|----------------------------------|---------------|---------------------------------------|---------------------|
| Chromium | 112 | (50 - 150) Dilution Factor: 1 | SW846 6010B | 09/10-09/15/99 | D28PE10G |
| Lead | 102 | (50 - 150) Dilution Factor: 1 | SW846 6010B | 09/10-09/15/99 | D28PE10H |
| Selenium | 100 | (50 - 150) Dilution Factor: 1 | SW846 6010B | 09/10-09/15/99 | D28PE109 |

NOTE (S) :

Calculations are performed before rounding to avoid round off errors in calculated results.

METHOD BLANK REPORT

GC/MS Volatiles

Client Lot #....: A9I020127

Work Order #....: D25PM101

Matrix.....: SOLID

MB Lot-Sample #: A9I070000-138

Prep Date.....: 09/07/99

Analysis Date...: 09/07/99

Prep Batch #....: 9250138

Dilution Factor: 1

| PARAMETER | RESULT | REPORTING | | | METHOD |
|----------------------|--------|-----------|-------|--|-------------|
| | | LIMIT | UNITS | | |
| Benzene | ND | 0.025 | mg/L | | SW846 8260B |
| Chlorobenzene | ND | 0.025 | mg/L | | SW846 8260B |
| 1,1-Dichloroethylene | ND | 0.070 | mg/L | | SW846 8260B |
| Trichloroethylene | ND | 0.050 | mg/L | | SW846 8260B |
| Carbon tetrachloride | ND | 0.025 | mg/L | | SW846 8260B |
| Chloroform | ND | 0.025 | mg/L | | SW846 8260B |
| 1,2-Dichloroethane | ND | 0.025 | mg/L | | SW846 8260B |
| Methyl ethyl ketone | ND | 20 | mg/L | | SW846 8260B |
| Tetrachloroethylene | ND | 0.070 | mg/L | | SW846 8260B |
| Vinyl chloride | ND | 0.050 | mg/L | | SW846 8260B |

| SURROGATE | PERCENT | | RECOVERY | |
|-----------------------|----------|--|------------|--|
| | RECOVERY | | LIMITS | |
| 1,2-Dichloroethane-d4 | 95 | | (75 - 117) | |
| Toluene-d8 | 99 | | (86 - 122) | |
| Bromofluorobenzene | 98 | | (60 - 137) | |
| Dibromofluoromethane | 103 | | (70 - 135) | |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC/MS Semivolatiles

Client Lot #...: A9I020127
 MB Lot-Sample #: A9I180000-107
 Leach Date.....: 09/08/99
 Leach Batch #...: P925102
 Dilution Factor: 1

Work Order #....: D2LL7101
 Prep Date.....: 09/18/99
 Prep Batch #....: 9261107

Matrix.....: SOLID
 Analysis Date...: 09/22/99

| PARAMETER | RESULT | REPORTING | | METHOD |
|-----------------------|--------|-----------|-------|-------------|
| | | LIMIT | UNITS | |
| o-Cresol | ND | 0.050 | mg/L | SW846 8270C |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L | SW846 8270C |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L | SW846 8270C |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachlorobenzene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachlorobutadiene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachloroethane | ND | 0.050 | mg/L | SW846 8270C |
| Nitrobenzene | ND | 0.050 | mg/L | SW846 8270C |
| Pentachlorophenol | ND | 0.10 | mg/L | SW846 8270C |
| Pyridine | ND | 0.10 | mg/L | SW846 8270C |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L | SW846 8270C |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L | SW846 8270C |

| SURROGATE | PERCENT | RECOVERY |
|----------------------|----------|------------|
| | RECOVERY | LIMITS |
| Nitrobenzene-d5 | 69 | (44 - 110) |
| 2-Fluorobiphenyl | 59 | (50 - 105) |
| Terphenyl-d14 | 75 | (11 - 158) |
| Phenol-d5 | 49 | (10 - 131) |
| 2-Fluorophenol | 60 | (10 - 130) |
| 2,4,6-Tribromophenol | 54 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC/MS Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D26JP101 Matrix.....: SOLID
 MB Lot-Sample #: A9I080000-149
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #....: 9251149
 Dilution Factor: 1

| PARAMETER | RESULT | REPORTING | | |
|-----------------------|--------|-----------|-------|-------------|
| | | LIMIT | UNITS | METHOD |
| o-Cresol | ND | 0.050 | mg/L | SW846 8270C |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L | SW846 8270C |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L | SW846 8270C |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachlorobenzene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachlorobutadiene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachloroethane | ND | 0.050 | mg/L | SW846 8270C |
| Nitrobenzene | ND | 0.050 | mg/L | SW846 8270C |
| Pentachlorophenol | ND | 0.10 | mg/L | SW846 8270C |
| Pyridine | ND | 0.10 | mg/L | SW846 8270C |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L | SW846 8270C |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 72 | (44 - 110) |
| 2-Fluorobiphenyl | 73 | (50 - 105) |
| Terphenyl-d14 | 110 | (11 - 158) |
| Phenol-d5 | 58 | (10 - 131) |
| 2-Fluorophenol | 52 | (10 - 130) |
| 2,4,6-Tribromophenol | 76 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC/MS Semivolatiles

Client Lot #....: A9I020127
 MB Lot-Sample #: A9I070000-215
 Leach Date.....: 09/04/99
 Leach Batch #...: P924701
 Dilution Factor: 1

Work Order #....: D2615101
 Prep Date.....: 09/08/99
 Prep Batch #...: 9250215

Matrix.....: SOLID
 Analysis Date...: 09/13/99

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD |
|-----------------------|--------|--------------------|-------|-------------|
| o-Cresol | ND | 0.050 | mg/L | SW846 8270C |
| m-Cresol & p-Cresol | ND | 0.10 | mg/L | SW846 8270C |
| 1,4-Dichlorobenzene | ND | 0.050 | mg/L | SW846 8270C |
| 2,4-Dinitrotoluene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachlorobenzene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachlorobutadiene | ND | 0.050 | mg/L | SW846 8270C |
| Hexachloroethane | ND | 0.050 | mg/L | SW846 8270C |
| Nitrobenzene | ND | 0.050 | mg/L | SW846 8270C |
| Pentachlorophenol | ND | 0.10 | mg/L | SW846 8270C |
| Pyridine | ND | 0.10 | mg/L | SW846 8270C |
| 2,4,5-Trichlorophenol | ND | 0.050 | mg/L | SW846 8270C |
| 2,4,6-Trichlorophenol | ND | 0.050 | mg/L | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 77 | (44 - 110) |
| 2-Fluorobiphenyl | 75 | (50 - 105) |
| Terphenyl-d14 | 108 | (11 - 158) |
| Phenol-d5 | 62 | (10 - 131) |
| 2-Fluorophenol | 41 | (10 - 130) |
| 2,4,6-Tribromophenol | 84 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D26JN101 Matrix.....: SOLID
 MB Lot-Sample #: A9I080000-148
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #...: 9251148
 Dilution Factor: 1

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD |
|-----------------------|--------|--------------------|-------|-------------|
| Chlordane (technical) | ND | 0.0050 | mg/L | SW846 8081A |
| Endrin | ND | 0.00050 | mg/L | SW846 8081A |
| Heptachlor | ND | 0.00050 | mg/L | SW846 8081A |
| Heptachlor epoxide | ND | 0.00050 | mg/L | SW846 8081A |
| Lindane | ND | 0.00050 | mg/L | SW846 8081A |
| Methoxychlor | ND | 0.0010 | mg/L | SW846 8081A |
| Toxaphene | ND | 0.020 | mg/L | SW846 8081A |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------|---------------------|--------------------|
| Decachlorobiphenyl | 86 | (60 - 150) |
| Tetrachloro-m-xylene | 81 | (14 - 155) |

NOTE (S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D260K101 Matrix.....: SOLID
 MB Lot-Sample #: A9I070000-211
 Leach Date.....: 09/04/99 Prep Date.....: 09/08/99 Analysis Date...: 09/11/99
 Leach Batch #...: P924701 Prep Batch #...: 9250211
 Dilution Factor: 1

| | | REPORTING | | |
|-----------------------|-----------------------------|----------------------------|--------------|---------------|
| <u>PARAMETER</u> | <u>RESULT</u> | <u>LIMIT</u> | <u>UNITS</u> | <u>METHOD</u> |
| Chlordane (technical) | ND | 0.0050 | mg/L | SW846 8081A |
| Endrin | ND | 0.00050 | mg/L | SW846 8081A |
| Heptachlor | ND | 0.00050 | mg/L | SW846 8081A |
| Heptachlor epoxide | ND | 0.00050 | mg/L | SW846 8081A |
| Lindane | ND | 0.00050 | mg/L | SW846 8081A |
| Methoxychlor | ND | 0.0010 | mg/L | SW846 8081A |
| Toxaphene | ND | 0.020 | mg/L | SW846 8081A |
| | | | | |
| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> | | |
| Decachlorobiphenyl | 83 | (60 - 150) | | |
| Tetrachloro-m-xylene | 79 | (14 - 155) | | |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC Semivolatiles

Client Lot #...: A9I020127
 MB Lot-Sample #: A9I090000-314
 Leach Date.....: 09/04/99
 Leach Batch #...: P924701
 Dilution Factor: 1

Work Order #...: D28WL101
 Prep Date.....: 09/10/99
 Prep Batch #...: 9252314

Matrix.....: SOLID

Analysis Date...: 09/17/99

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD |
|-------------------------------|----------|--------------------|-------|-------------|
| 2,4-D | ND | 0.50 | mg/L | SW846 8151A |
| 2,4,5-TP (Silvex) | ND | 0.10 | mg/L | SW846 8151A |
| SURROGATE | PERCENT | RECOVERY | | |
| 2,4-Dichlorophenylacetic acid | RECOVERY | LIMITS | | |
| | 81 | (53 - 168) | | |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP GC Semivolatiles

Client Lot #...: A9I020127
 MB Lot-Sample #: A9I090000-316
 Leach Date.....: 09/08/99
 Leach Batch #...: P925102
 Dilution Factor: 1

Work Order #...: D28WT101
 Prep Date.....: 09/10/99
 Prep Batch #...: 9252316

Matrix.....: SOLID
 Analysis Date...: 09/17/99

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD |
|-------------------------------|----------|--------------------|-------|-------------|
| 2,4-D | ND | 0.50 | mg/L | SW846 8151A |
| 2,4,5-TP (Silvex) | ND | 0.10 | mg/L | SW846 8151A |
| SURROGATE | PERCENT | RECOVERY | | |
| 2,4-Dichlorophenylacetic acid | RECOVERY | LIMITS | | |
| | 72 | (53 - 168) | | |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP Metals

Client Lot #...: A9I020127

Matrix.....: SOLID

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|--|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| MB lot-Sample #: A9I040000-101 Prep Batch #...: 9251209 | | | | | | |
| Leach Date.....: 09/04/99 Leach Batch #...: P924701 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM104 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM105 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM106 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM107 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM108 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM101 |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/09-09/10/99 | D24XM103 |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D24XM102 |
| | | Dilution Factor: 1 | | | | |
| | | | | | | |
| MB lot-Sample #: A9I080000-272 Prep Batch #...: 9252299 | | | | | | |
| Leach Date.....: 09/08/99 Leach Batch #...: P925102 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783104 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783105 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783106 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783107 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783108 |
| | | Dilution Factor: 1 | | | | |

(Continued on next page)

METHOD BLANK REPORT

TCLP Metals

Client Lot #....: A9I020127

Matrix.....: SOLID

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|-----------|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783101 |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/10-09/11/99 | D2783103 |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D2783102 |
| | | Dilution Factor: 1 | | | | |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

TCLP Metals

Client Lot #...: A9I020127

Matrix.....: SOLID

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|--|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| MB Lot-Sample #: A9I080000-209 Prep Batch #....: 9251209 | | | | | | |
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV104 |
| | | Dilution Factor: 1 | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV105 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV106 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV107 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV108 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV101 |
| | | Dilution Factor: 1 | | | | |
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/09-09/10/99 | D26QV103 |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/09-09/15/99 | D26QV102 |
| | | Dilution Factor: 1 | | | | |

MB Lot-Sample #: A9I090000-299 Prep Batch #....: 9252299

| | | | | | | |
|----------|----|---------------------|------|-------------|----------------|----------|
| Arsenic | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE104 |
| | | Dilution Factor: 1. | | | | |
| Barium | ND | 10.0 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE105 |
| | | Dilution Factor: 1 | | | | |
| Cadmium | ND | 0.10 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE106 |
| | | Dilution Factor: 1 | | | | |
| Chromium | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE107 |
| | | Dilution Factor: 1 | | | | |
| Lead | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE108 |
| | | Dilution Factor: 1 | | | | |
| Selenium | ND | 0.25 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE101 |
| | | Dilution Factor: 1 | | | | |

(Continued on next page)

METHOD BLANK REPORT

TCLP Metals

Client Lot #...: A9I020127

Matrix.....: SOLID

| <u>PARAMETER</u> | <u>RESULT</u> | <u>REPORTING LIMIT</u> | <u>UNITS</u> | <u>METHOD</u> | <u>PREPARATION- ANALYSIS DATE</u> | <u>WORK ORDER #</u> |
|------------------|---------------|----------------------------|--------------|---------------|---------------------------------------|-------------------------|
| Mercury | ND | 0.0020 | mg/L | SW846 7470A | 09/10-09/11/99 | D28PE103 |
| | | Dilution Factor: 1 | | | | |
| Silver | ND | 0.50 | mg/L | SW846 6010B | 09/10-09/15/99 | D28PE102 |
| | | Dilution Factor: 1 | | | | |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

METHOD BLANK REPORT

General Chemistry

Client Lot #....: A9I020127

Matrix.....: WASTE

| PARAMETER | RESULT | REPORTING LIMIT | UNITS | METHOD | PREPARATION- ANALYSIS DATE | PREP BATCH # |
|------------------|--------|--------------------|-------|-------------|-------------------------------|-----------------|
| Reactive Cyanide | ND | 200 | mg/kg | SW846 7.3.3 | 09/14-09/19/99 | 9262118 |
| | | Dilution Factor: 1 | | | | |
| Reactive Sulfide | ND | 200 | mg/kg | SW846 7.3.4 | 09/14-09/19/99 | 9262116 |
| | | Dilution Factor: 1 | | | | |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC/MS Volatiles

Client Lot #...: A9I020127 Work Order #...: D22LX102-MS Matrix.....: SOLID
 MS Lot-Sample #: A9I020177-001 D22LX103-MSD
 Date Sampled...: 09/01/99 14:04 Date Received...: 09/02/99
 Leach Date.....: 09/03/99 Prep Date.....: 09/07/99 Analysis Date...: 09/07/99
 Leach Batch #...: P924508 Prep Batch #...: 9250138
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|----------------------|---------------------|--------------------|-----|---------------|-------------|
| 1,1-Dichloroethylene | 100 | (75 - 131) | | | SW846 8260B |
| | 101 | (75 - 131) | 1.1 | (0-17) | SW846 8260B |
| Trichloroethylene | 93 | (78 - 121) | | | SW846 8260B |
| | 95 | (78 - 121) | 1.8 | (0-17) | SW846 8260B |
| Chlorobenzene | 96 | (76 - 122) | | | SW846 8260B |
| | 101 | (76 - 122) | 5.0 | (0-22) | SW846 8260B |
| Benzene | 103 | (84 - 121) | | | SW846 8260B |
| | 107 | (84 - 121) | 4.0 | (0-13) | SW846 8260B |
| Toluene | 96 | (79 - 129) | | | SW846 8260B |
| | 99 | (79 - 129) | 2.4 | (0-23) | SW846 8260B |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-----------------------|---------------------|--------------------|
| 1,2-Dichloroethane-d4 | 90 | (75 - 117) |
| | 92 | (75 - 117) |
| Toluene-d8 | 95 | (86 - 122) |
| | 100 | (86 - 122) |
| Bromofluorobenzene | 98 | (60 - 137) |
| | 101 | (60 - 137) |
| Dibromofluoromethane | 98 | (70 - 135) |
| | 97 | (70 - 135) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC/MS Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D225A10L-MS Matrix.....: SOLID
 MS Lot-Sample #: A9I020127-004 D225A10M-MSD
 Date Sampled...: 08/26/99 16:00 Date Received...: 09/02/99
 Leach Date.....: 09/08/99 Prep Date.....: 09/09/99 Analysis Date...: 09/14/99
 Leach Batch #...: P925102 Prep Batch #...: 9251149
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|-----------------------|---------------------|--------------------|-----|---------------|-------------|
| o-Cresol | 69 | (46 - 109) | | | SW846 8270C |
| | 45 a,p | (46 - 109) | 41 | (0-32) | SW846 8270C |
| m-Cresol & p-Cresol | 69 | (46 - 109) | | | SW846 8270C |
| | 45 a,p | (46 - 109) | 43 | (0-32) | SW846 8270C |
| 1,4-Dichlorobenzene | 63 | (34 - 105) | | | SW846 8270C |
| | 42 p | (34 - 105) | 41 | (0-21) | SW846 8270C |
| 2,4-Dinitrotoluene | 73 | (10 - 154) | | | SW846 8270C |
| | 48 | (10 - 154) | 41 | (0-42) | SW846 8270C |
| Hexachlorobenzene | 95 | (33 - 123) | | | SW846 8270C |
| | 63 p | (33 - 123) | 40 | (0-23) | SW846 8270C |
| Hexachlorobutadiene | 66 | (27 - 107) | | | SW846 8270C |
| | 45 p | (27 - 107) | 38 | (0-24) | SW846 8270C |
| Hexachloroethane | 58 | (24 - 107) | | | SW846 8270C |
| | 39 p | (24 - 107) | 38 | (0-20) | SW846 8270C |
| Nitrobenzene | 79 | (40 - 118) | | | SW846 8270C |
| | 54 p | (40 - 118) | 37 | (0-25) | SW846 8270C |
| Pentachlorophenol | 48 | (10 - 148) | | | SW846 8270C |
| | 29 | (10 - 148) | 48 | (0-75) | SW846 8270C |
| Pyridine | 55 | (22 - 96) | | | SW846 8270C |
| | 39 | (22 - 96) | 34 | (0-52) | SW846 8270C |
| 2,4,5-Trichlorophenol | 67 | (25 - 136) | | | SW846 8270C |
| | 42 | (25 - 136) | 46 | (0-62) | SW846 8270C |
| 2,4,6-Trichlorophenol | 73 | (20 - 127) | | | SW846 8270C |
| | 47 | (20 - 127) | 44 | (0-55) | SW846 8270C |
| Cresols (total) | 69 | (22 - 115) | | | SW846 8270C |
| | 45 | (22 - 115) | 42 | (0-43) | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|-----------------|---------------------|--------------------|
| Nitrobenzene-d5 | 76 | (44 - 110) |
| | 53 | (44 - 110) |
| Fluorobiphenyl | 77 | (50 - 105) |
| | 52 | (50 - 105) |
| Terphenyl-d14 | 127 | (11 - 158) |
| | 88 | (11 - 158) |
| Phenol-d5 | 59 | (10 - 131) |
| | 35 | (10 - 131) |
| 2-Fluorophenol | 47 | (10 - 130) |
| | 18 | (10 - 130) |

(Continued on next page)

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC/MS Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D225A10L-MS Matrix.....: SOLID
MS Lot-Sample #: A9I020127-004 D225A10M-MSD

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|----------------------|-----------------------------|----------------------------|
| 2,4,6-Tribromophenol | 80 | (10 - 156) |
| | 50 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Hold print denotes control parameters

a Spiked analyte recovery is outside stated control limits.

p Relative percent difference (RPD) is outside stated control limits.

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC/MS Semivolatiles

Client Lot #....: A9I020127 Work Order #....: D225210L-MS Matrix.....: SOLID
 MS Lot-Sample #: A9I020127-001 D225210M-MSD
 Date Sampled....: 08/23/99 14:00 Date Received...: 09/02/99
 Leach Date.....: 09/04/99 Prep Date.....: 09/08/99 Analysis Date...: 09/13/99
 Leach Batch #...: P924701 Prep Batch #....: 9250215
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|-----------------------|---------------------|--------------------|------|---------------|-------------|
| o-Cresol | 37 a | (46 - 109) | | | SW846 8270C |
| | 55 p | (46 - 109) | 40 | (0-32) | SW846 8270C |
| m-Cresol & p-Cresol | 47 | (46 - 109) | | | SW846 8270C |
| | 59 | (46 - 109) | 22 | (0-32) | SW846 8270C |
| 1,4-Dichlorobenzene | 65 | (34 - 105) | | | SW846 8270C |
| | 62 | (34 - 105) | 4.8 | (0-21) | SW846 8270C |
| 2,4-Dinitrotoluene | 78 | (10 - 154) | | | SW846 8270C |
| | 76 | (10 - 154) | 2.8 | (0-42) | SW846 8270C |
| Hexachlorobenzene | 89 | (33 - 123) | | | SW846 8270C |
| | 89 | (33 - 123) | 0.65 | (0-23) | SW846 8270C |
| Hexachlorobutadiene | 67 | (27 - 107) | | | SW846 8270C |
| | 63 | (27 - 107) | 5.2 | (0-24) | SW846 8270C |
| Hexachloroethane | 63 | (24 - 107) | | | SW846 8270C |
| | 59 | (24 - 107) | 7.3 | (0-20) | SW846 8270C |
| Nitrobenzene | 78 | (40 - 118) | | | SW846 8270C |
| | 75 | (40 - 118) | 4.7 | (0-25) | SW846 8270C |
| Pentachlorophenol | 75 | (10 - 148) | | | SW846 8270C |
| | 72 | (10 - 148) | 5.0 | (0-75) | SW846 8270C |
| Pyridine | 46 | (22 - 96) | | | SW846 8270C |
| | 38 | (22 - 96) | 19 | (0-52) | SW846 8270C |
| 2,4,5-Trichlorophenol | 75 | (25 - 136) | | | SW846 8270C |
| | 73 | (25 - 136) | 2.6 | (0-62) | SW846 8270C |
| 2,4,6-Trichlorophenol | 72 | (20 - 127) | | | SW846 8270C |
| | 71 | (20 - 127) | 0.97 | (0-55) | SW846 8270C |
| Cresols (total) | 44 | (22 - 115) | | | SW846 8270C |
| | 58 | (22 - 115) | 28 | (0-43) | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 77 | (44 - 110) |
| | 74 | (44 - 110) |
| 2-Fluorobiphenyl | 77 | (50 - 105) |
| | 74 | (50 - 105) |
| Terphenyl-d14 | 116 | (11 - 158) |
| | 111 | (11 - 158) |
| Phenol-d5 | 58 | (10 - 131) |
| | 52 | (10 - 131) |
| 2-Fluorophenol | 38 | (10 - 130) |
| | 26 | (10 - 130) |

(Continued on next page)

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC/MS Semivolatiles

Client Lot #...: A9I020127

Work Order #...: D225210L-MS

Matrix.....: SOLID

MS Lot-Sample #: A9I020127-001

D225210M-MSD

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|----------------------|-----------------------------|----------------------------|
| 2,4,6-Tribromophenol | 80 | (10 - 156) |
| | 80 | (10 - 156) |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

bold print denotes control parameters

p Relative percent difference (RPD) is outside stated control limits.

a Spiked analyte recovery is outside stated control limits.

MATRIX SPIKE SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D225710M-MS Matrix.....: SOLID
 MS Lot-Sample #: A9I020127-003 D225710N-MSD
 Date Sampled...: 08/25/99 17:00 Date Received...: 09/02/99
 Prep Date.....: 09/18/99 Analysis Date...: 09/22/99
 Prep Batch #...: 9261107
 Dilution Factor: 1 % Moisture.....:

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|-----------------------|---------------------|--------------------|-----|---------------|-------------|
| o-Cresol | 10 a | (46 - 109) | | | SW846 8270C |
| | 10 a | (46 - 109) | 2.7 | (0-32) | SW846 8270C |
| m-Cresol & p-Cresol | 12 a | (46 - 109) | | | SW846 8270C |
| | 11 a | (46 - 109) | 7.2 | (0-32) | SW846 8270C |
| 1,4-Dichlorobenzene | 55 | (34 - 105) | | | SW846 8270C |
| | 52 | (34 - 105) | 5.2 | (0-21) | SW846 8270C |
| 2,4-Dinitrotoluene | 49 | (10 - 154) | | | SW846 8270C |
| | 51 | (10 - 154) | 3.0 | (0-42) | SW846 8270C |
| Hexachlorobenzene | 70 | (33 - 123) | | | SW846 8270C |
| | 69 | (33 - 123) | 1.5 | (0-23) | SW846 8270C |
| Hexachlorobutadiene | 61 | (27 - 107) | | | SW846 8270C |
| | 57 | (27 - 107) | 5.9 | (0-24) | SW846 8270C |
| Hexachloroethane | 58 | (24 - 107) | | | SW846 8270C |
| | 55 | (24 - 107) | 5.2 | (0-20) | SW846 8270C |
| Nitrobenzene | 63 | (40 - 118) | | | SW846 8270C |
| | 61 | (40 - 118) | 3.2 | (0-25) | SW846 8270C |
| Pentachlorophenol | 31 | (10 - 148) | | | SW846 8270C |
| | 39 | (10 - 148) | 24 | (0-75) | SW846 8270C |
| Pyridine | 41 | (22 - 96) | | | SW846 8270C |
| | 39 | (22 - 96) | 5.3 | (0-52) | SW846 8270C |
| 2,4,5-Trichlorophenol | 27 | (25 - 136) | | | SW846 8270C |
| | 31 | (25 - 136) | 15 | (0-62) | SW846 8270C |
| 2,4,6-Trichlorophenol | 31 | (20 - 127) | | | SW846 8270C |
| | 33 | (20 - 127) | 5.6 | (0-55) | SW846 8270C |
| Cresols (total) | 11 a | (22 - 115) | | | SW846 8270C |
| | 11 a | (22 - 115) | 5.8 | (0-43) | SW846 8270C |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|------------------|---------------------|--------------------|
| Nitrobenzene-d5 | 65 | (44 - 110) |
| | 63 | (44 - 110) |
| 2-Fluorobiphenyl | 54 | (50 - 105) |
| | 55 | (50 - 105) |
| Terphenyl-d14 | 70 | (11 - 158) |
| | 70 | (11 - 158) |
| Phenol-d5 | 12 | (10 - 131) |
| | 11 | (10 - 131) |
| 2-Fluorophenol | 13 | (10 - 130) |
| | 12 | (10 - 130) |

(Continued on next page)

MATRIX SPIKE SAMPLE EVALUATION REPORT

GC/MS Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D225710M-MS Matrix.....: SOLID
MS Lot-Sample #: A9I020127-003 D225710N-MSD

| <u>SURROGATE</u> | <u>PERCENT RECOVERY</u> | <u>RECOVERY LIMITS</u> |
|----------------------|-----------------------------|----------------------------|
| 2,4,6-Tribromophenol | 36 | (10 - 156) |
| | 38 | (10 - 156) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

a Spiked analyte recovery is outside stated control limits.

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D2252117-MS Matrix.....: SOLID
 MS Lot-Sample #: A9I020127-001 D2252118-MSD
 Date Sampled...: 08/23/99 14:00 Date Received...: 09/02/99
 Leach Date.....: 09/04/99 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
 Leach Batch #...: P924701 Prep Batch #...: 9252314
 Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|-------------------|---------------------|--------------------|-----|---------------|-------------|
| 2,4-D | 86 | (39 - 138) | | | SW846 8151A |
| | 85 | (39 - 138) | 1.4 | (0-20) | SW846 8151A |
| 2,4,5-TP (Silvex) | 81 | (43 - 102) | | | SW846 8151A |
| | 78 | (43 - 102) | 3.2 | (0-18) | SW846 8151A |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------------------|---------------------|--------------------|
| 2,4-Dichlorophenylacetic acid | 78 | (53 - 168) |
| | 79 | (53 - 168) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.

Bold print denotes control parameters

ON
Inventory

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP GC Semivolatiles

Client Lot #...: A9I020127 Work Order #...: D2256115-MS Matrix.....: SOLID
MS Lot-Sample #: A9I020127-002 D2256116-MSD
Date Sampled...: 08/24/99 11:00 Date Received...: 09/02/99
Leach Date.....: 09/08/99 Prep Date.....: 09/10/99 Analysis Date...: 09/17/99
Leach Batch #...: P925102 Prep Batch #...: 9252316
Dilution Factor: 1

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD | RPD LIMITS | METHOD |
|-------------------|---------------------|--------------------|-----|---------------|-------------|
| 2,4-D | 79 | (39 - 138) | | | SW846 8151A |
| | 78 | (39 - 138) | 1.4 | (0-20) | SW846 8151A |
| 2,4,5-TP (Silvex) | 75 | (43 - 102) | | | SW846 8151A |
| | 78 | (43 - 102) | 4.1 | (0-18) | SW846 8151A |

| SURROGATE | PERCENT RECOVERY | RECOVERY LIMITS |
|----------------------------------|---------------------|--------------------|
| 2,4-Dichlorophenylacetic acid | 75 | (53 - 168) |
| | 75 | (53 - 168) |

NOTE(S) :

Calculations are performed before rounding to avoid round-off errors in calculated results.
Bold print denotes control parameters

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP Metals

Client Lot #....: A9I020127

Matrix.....: SOLID

Date Sampled....: 08/23/99 14:00 Date Received...: 09/02/99

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD LIMITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|--|---------------------|--------------------|---------------|-------------|-------------------------------|-----------------|
| MS Lot-Sample #: A9I020127-001 Prep Batch #....: 9251209 | | | | | | |
| Leach Date.....: 09/04/99 Leach Batch #...: P924701 | | | | | | |
| Arsenic | 104 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D225210V |
| | 104 | (50 - 150) | 0.48 (0-20) | SW846 6010B | 09/09-09/15/99 | D225210W |
| Dilution Factor: 1 | | | | | | |
| Barium | 99 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D225210X |
| | 98 | (50 - 150) | 0.70 (0-20) | SW846 6010B | 09/09-09/15/99 | D2252110 |
| Dilution Factor: 1 | | | | | | |
| Cadmium | 100 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D2252111 |
| | 99 | (50 - 150) | 0.76 (0-20) | SW846 6010B | 09/09-09/15/99 | D2252112 |
| Dilution Factor: 1 | | | | | | |
| Chromium | 100 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D2252113 |
| | 100 | (50 - 150) | 0.52 (0-20) | SW846 6010B | 09/09-09/15/99 | D2252114 |
| Dilution Factor: 1 | | | | | | |
| Lead | 100 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D2252115 |
| | 99 | (50 - 150) | 1.0 (0-20) | SW846 6010B | 09/09-09/15/99 | D2252116 |
| Dilution Factor: 1 | | | | | | |
| Selenium | 112 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D225210N |
| | 111 | (50 - 150) | 1.6 (0-20) | SW846 6010B | 09/09-09/15/99 | D225210P |
| Dilution Factor: 1 | | | | | | |
| Mercury | 91 | (50 - 150) | | SW846 7470A | 09/09-09/10/99 | D225210T |
| | 87 | (50 - 150) | 4.1 (0-20) | SW846 7470A | 09/09-09/10/99 | D225210U |
| Dilution Factor: 1 | | | | | | |
| Silver | 100 | (50 - 150) | | SW846 6010B | 09/09-09/15/99 | D225210Q |
| | 100 | (50 - 150) | 0.52 (0-20) | SW846 6010B | 09/09-09/15/99 | D225210R |
| Dilution Factor: 1 | | | | | | |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

MATRIX SPIKE SAMPLE EVALUATION REPORT

TCLP Metals

Client Lot #...: A9I020127

Matrix.....: SOLID

Date Sampled...: 08/24/99 11:00 Date Received...: 09/02/99

| PARAMETER | PERCENT RECOVERY | RECOVERY LIMITS | RPD LIMITS | METHOD | PREPARATION- ANALYSIS DATE | WORK ORDER # |
|---|---------------------|--------------------|---------------|-------------|-------------------------------|-----------------|
| MS Lot-Sample #: A9I020127-002 Prep Batch #...: 9252299 | | | | | | |
| Leach Date.....: 09/08/99 Leach Batch #...: P925102 | | | | | | |
| Arsenic | 105 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D225610T |
| | 104 | (50 - 150) 0.82 | (0-20) | SW846 6010B | 09/10-09/15/99 | D225610U |
| Dilution Factor: 1 | | | | | | |
| Barium | 99 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D225610V |
| | 99 | (50 - 150) 0.36 | (0-20) | SW846 6010B | 09/10-09/15/99 | D225610W |
| Dilution Factor: 1 | | | | | | |
| Cadmium | 101 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D225610X |
| | 101 | (50 - 150) 0.22 | (0-20) | SW846 6010B | 09/10-09/15/99 | D2256110 |
| Dilution Factor: 1 | | | | | | |
| Chromium | 102 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D2256111 |
| | 101 | (50 - 150) 0.66 | (0-20) | SW846 6010B | 09/10-09/15/99 | D2256112 |
| Dilution Factor: 1 | | | | | | |
| Lead | 100 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D2256113 |
| | 100 | (50 - 150) 0.13 | (0-20) | SW846 6010B | 09/10-09/15/99 | D2256114 |
| Dilution Factor: 1 | | | | | | |
| Selenium | 114 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D225610L |
| | 118 | (50 - 150) 2.9 | (0-20) | SW846 6010B | 09/10-09/15/99 | D225610M |
| Dilution Factor: 1 | | | | | | |
| Mercury | 90 | (50 - 150) | | SW846 7470A | 09/10-09/11/99 | D225610Q |
| | 93 | (50 - 150) 3.0 | (0-20) | SW846 7470A | 09/10-09/11/99 | D225610R |
| Dilution Factor: 1 | | | | | | |
| Silver | 99 | (50 - 150) | | SW846 6010B | 09/10-09/15/99 | D225610N |
| | 100 | (50 - 150) 0.68 | (0-20) | SW846 6010B | 09/10-09/15/99 | D225610P |
| Dilution Factor: 1 | | | | | | |

NOTE(S):

Calculations are performed before rounding to avoid round-off errors in calculated results.

General Chemistry

Matrix.....: WASTE

Moisture.....: 100

| | | | | | |
|------------------|----|--------------------|---|--------|------------------------------------|
| Reactive Cyanide | | | | | SD Lot-Sample #: A9I020121-001 |
| ND | ND | mg/kg | 0 | (0-20) | SW846 7.3.3 09/14-09/19/99 9262118 |
| | | Dilution Factor: 1 | | | |

General Chemistry

Matrix.....: SOLID

‡ Moisture.....:

| PARAM | RESULT | DUPLICATE RESULT | UNITS | RPD | RPD LIMIT | METHOD | PREPARATION- ANALYSIS DATE | PREP BATCH # |
|------------------|--------|---------------------|--------------------|------|--------------|------------------|-------------------------------|-----------------|
| Reactive Cyanide | | | | | | SD Lot-Sample #: | A9I020127-002 | |
| ND | ND | | mg/kg | 0 | (0-20) | SW846 7.3.3 | 09/14-09/19/99 | 9262118 |
| | | | Dilution Factor: 1 | | | | | |
| Reactive Sulfide | | | | | | SD Lot-Sample #: | A9I020127-002 | |
| ND | ND | | mg/kg | 0 | (0-20) | SW846 7.3.4 | 09/14-09/19/99 | 9262116 |
| | | | Dilution Factor: 1 | | | | | |
| pH (solid) | | | | | | SD Lot-Sample #: | A9I020127-002 | |
| 8.8 | 8.8 | | No Units | 0.23 | (0-20) | SW846 9045C | 09/02/99 | 9252464 |
| | | | Dilution Factor: 1 | | | | | |


[illegible]

100

100

100





A 2664

PSARA TECHNOLOGIES, INC. 10925 Reed Hartman Highway • Suite 220 • Cincinnati, Ohio 45242 • (513) 791-4418 • Fax (513) 791-5797

WHITE - Accompanies Samples
YELLOW - Laboratory Copy
PINK - Office/Field Copy